

**CITY OF LA VISTA  
MAYOR AND CITY COUNCIL REPORT  
APRIL 5, 2022 AGENDA**

<b>Subject:</b>	<b>Type:</b>	<b>Submitted By:</b>
REPLAT & SUBDIVISION AGREEMENT – ECHO HILLS REPLAT FIVE	◆ RESOLUTIONS (2) ORDINANCE RECEIVE/FILE	CALE BRODERSEN ASSISTANT CITY PLANNER

**SYNOPSIS**

Resolutions have been prepared for Council to consider a replat and subdivision agreement by applicant West Management, LLC for approximately 8.65 acres northwest of the intersection of S 144<sup>th</sup> Street and Chandler Road. Lots 2-4 Echo Hills Replat Four would be replatted into Lot 1 Echo Hills Replat Five so that the Echo Hills Apartments (both existing and proposed buildings) would all be on one legal lot.

**FISCAL IMPACT**

N/A.

**RECOMMENDATION**

Approval.

**BACKGROUND**

On April 21, 2020, Council approved the Final Plat for Echo Hills Replat Four for a development proposal with an assisted living and memory care facility on Lot 1, four apartment buildings on lot 2, and a proposed commercial development on Lots 3 and 4. The applicant is applying to construct a fifth apartment building on Lots 3 and 4 Echo Hills Replat Four. This application would combine Lots 2-4 Echo Hills Replat Four into Lot 1 Echo Hills Replat Five so that all of the apartment buildings would be on one legal lot.

Accompanying this application for a Replat is a revised Subdivision Agreement to account for the changes from the original development concept including the site plan, utility locations, updates to the stormwater and sewer connection fees, etc. A detailed staff report is attached.

The Planning Commission held a public hearing on March 3, 2022, and unanimously voted to recommend approval of the Replat, subject to satisfaction of all applicable requirements, including without limitation, notice, hearing, and approval of amendments to the Comprehensive Plan Future Land Use Map, Official Zoning Map, Planned Unit Development, and Conditional Use Permit, and approval and recording of the subdivision agreement.

**RESOLUTION NO. \_\_\_\_\_**

A RESOLUTION OF THE MAYOR AND CITY COUNCIL OF THE CITY OF LA VISTA, NEBRASKA, FOR APPROVAL OF THE REPLAT FOR LOTS 2-4 ECHO HILLS REPLAT FOUR, TO BE REPLATTED AS LOT 1 ECHO HILLS REPLAT FIVE, A SUBDIVISION LOCATED IN THE SOUTHEAST QUARTER OF THE NORTHEAST QUARTER OF SECTION 14, TOWNSHIP 14 NORTH, RANGE 11 EAST OF THE 6TH P.M., IN SARPY COUNTY, NEBRASKA.

WHEREAS, the owners of the above described property applied for approval of a replat for Lots 2-4 Echo Hills Replat Four, to be replatted as Lot 1 Echo Hills Replat Five; and

WHEREAS, the City Engineer has reviewed the replat; and

WHEREAS, on March 3, 2022, the La Vista Planning Commission held a meeting and reviewed the replat and recommended approval.

NOW THEREFORE, BE IT RESOLVED by the Mayor and City Council of the City of La Vista, Nebraska, that the replat for Lots 2-4 Echo Hills Replat Four, to be replatted as Lot 1 Echo Hills Replat Five, a subdivision located in the southeast quarter of the northeast quarter of Section 14, Township 14 North, Range 11 East of the 6<sup>th</sup> P.M., Sarpy County, Nebraska, generally located northwest of the intersection of S 144<sup>th</sup> Street and Chandler Road, be, and hereby is, approved, subject to adoption and execution of the corresponding Subdivision Agreement amendment presented at this Council meeting.

PASSED AND APPROVED THIS 5TH DAY OF APRIL 2022.

CITY OF LA VISTA

ATTEST:

---

Kim J. Thomas, Acting Mayor

---

Pamela A. Buethe, MMC  
City Clerk

**RESOLUTION NO. \_\_\_\_\_**

A RESOLUTION OF THE MAYOR AND CITY COUNCIL OF THE CITY OF LA VISTA, NEBRASKA APPROVING AN AMENDMENT TO THE SUBDIVISION AGREEMENT FOR ECHO HILLS REPLAT FOUR.

WHEREAS, the City Council did on April 5, 2022, approve of Echo Hills Replat Five subject to certain conditions; and

WHEREAS, the Subdivider, West Management, LLC o.b.o. Vandelay Investments, LLC, Echo Hills Apartments, LLC, and Echo Hills ALMC, LLC, as owner(s) of the affected lots agreed to execute an amendment to the original Subdivision Agreement satisfactory in form and content to the City;

NOW THEREFORE, BE IT RESOLVED, that the Subdivision Agreement be and hereby is approved and the Mayor and City Clerk be and hereby are authorized to execute the same on behalf of the City, subject to any specified conditions of Council and any revisions that the City Administrator or City Engineer may determine necessary or advisable.

PASSED AND APPROVED THIS 5TH DAY OF APRIL 2022.

CITY OF LA VISTA

---

Kim J. Thomas, Acting Mayor

ATTEST:

---

Pamela A. Buethe, MMC  
City Clerk



**CITY OF LA VISTA  
PLANNING DIVISION  
RECOMMENDATION REPORT**

---

CASE NUMBERS: PRP22-0001;

FOR HEARING ON: APRIL 5, 2022  
REPORT PREPARED ON: MARCH 22, 2022

**I. GENERAL INFORMATION**

**A. APPLICANT(S):**

West Management, LLC  
Attn: Brett West  
129 N 10<sup>th</sup> Street, #106  
Lincoln, NE 68508

**B. PROPERTY OWNERS:**

Vandelay Investments, LLC  
Attn: Brett West  
PO Box 22151  
Lincoln, NE 68542

Echo Hills Apartments, LLC  
Attn: Brett West  
129 N 10<sup>th</sup> Street, #106  
Lincoln, NE 68508

**C. LOCATION:** 7631 S 146<sup>th</sup> Street, La Vista, NE 68138, generally located northwest of the intersection of 144<sup>th</sup> Street and Chandler Road.

**D. LEGAL DESCRIPTION:** Lots 2-4 Echo Hills Replat Four.

**E. REQUESTED ACTION(S):** Approval of a replat to combine Lots 2-4 Echo Hills Replat Four, being replatted as Lot 1 Echo Hills Replat Five to accommodate the Echo Park Apartment complex on one lot.

**F. EXISTING ZONING AND LAND USE:** C-1 Shopping Center Commercial, Planned Unit Development (Overlay District), and Gateway Corridor District (Overlay District). This property is currently vacant.

**G. PURPOSE OF REQUEST:** Applicant is seeking to construct an additional apartment building as part of the Echo Park Apartments complex (building #5). The building would include 71 units, 16 tuck-under garages, and an 1,800 square foot retail space for a coffee shop user on the first floor on the westernmost edge of the building. With the construction of proposed building #5, the Echo Park Apartments would have a total of 281 units.

H. **SIZE OF SITE:** Approximately 8.65 acres.

**II. BACKGROUND INFORMATION**

**A. GENERAL NEIGHBORHOOD/AREA LAND USES AND ZONING:**

<u>Direction From Subject Property</u>	<u>Future Land Use Designation</u>	<u>Current Zoning Designation</u>	<u>Surrounding Development</u>
North	Medium-Density Residential and High-Density Residential	RS-72 Single-Family Residential (Sarpy County Zoning); R-3 High-Density Residential, PUD, and Gateway Corridor District (Overlay District)	Echo Hills Neighborhood and Echo Hills Assisted Living and Memory Care
East	Commercial	C-1 Shopping Center Commercial and Gateway Corridor District (Overlay District).	Dino's Storage
South	Industrial	I-1 Light Industrial and Gateway Corridor District (Overlay District).	Vacant
West	Medium-Density Residential	RS-72 Single-Family Residential (Sarpy County Zoning)	Echo Hills Neighborhood

**B. RELEVANT CASE HISTORY:**

1. On February 4, 2020 the City Council of the City of La Vista approved a Comprehensive Plan Future Land Use Map amendment, rezoning, planned unit development site plan, and replat for Lot 3 Echo Hills (replatted as Lots 1 through 4 Echo Hills Replat Four) for the development of an assisted living and memory care facility, apartments, and commercial development. Shortly thereafter, conditional use permits were approved for the apartments and assisted living facilities.
2. On May 26, 2020 the applicant requested an amendment to the PUD Site Plan relating to the amount and configuration of the provided off-street parking. Further design of the buildings necessitated a reduction in the number of provided stalls from 352 stalls on Lot 2 to 337 stalls in addition to the removal of one stall on Lot 1. Since the proposed number of parking stalls still greatly exceeded the number required by the La Vista Zoning Ordinance, this change was considered minor, qualified for administrative approval, and was approved by the City Administrator.

3. An additional amendment to the PUD Site Plan relating to the off-street parking was requested by the applicant on July 14, 2020. This request removed 28 stalls from the parking count on Lot 2 Echo Hills Replat Four. The space for these stalls still exists, but the stalls would not be striped or counted in the total parking count to reduce confusion and the likelihood that parked cars would block access to the attached parking garages in apartment buildings #1 and #2. Like the previous request, the updated proposed number of parking stalls still exceeded the number required by the La Vista Zoning Ordinance. As a minor change, this request qualified for administrative approval, and was approved by the City Administrator.
4. On September 15, 2020, City Council approved an amendment to the PUD site plan that allowed for alternative parking stall dimensions for the 91 stalls in the underground parking garage under apartment building #3 on Lot 2. Standard configurations for 90-degree parking stalls, per Section 7.09 of the La Vista Zoning Ordinance are 9' wide by 18' deep with an isle width of 24' for two-way traffic. The revised, approved dimensions for the underground garage stalls include a 22'-4" drive isle width (a 1'6" reduction), and some stalls with a depth of 17' (a 1' reduction). Other stalls in the garage will have a depth of 19'-6" (an increase of 1'-6").
5. Construction has been completed on the Echo Hills Assisted Living and Memory Care facility and the Echo Park Apartments buildings #1 and #2. Construction on the Echo Park Apartments buildings #3 and #4 is underway.

**C. APPLICABLE REGULATIONS:**

1. Section 5.08 of the City of La Vista Zoning Ordinance – R-3 High Density Residential
2. Section 5.10 of the City of La Vista Zoning Ordinance – C-1 Shopping Center Commercial
3. Section 5.15 of the City of La Vista Zoning Ordinance – PUD Planned Unit Development District (Overlay District)
4. Section 5.17 of the City of La Vista Zoning Ordinance – Gateway Corridor District (Overlay District)
5. Article 6 of the City of La Vista Zoning Ordinance – Conditional Use Permits
6. La Vista Subdivision Regulations.

### **III. ANALYSIS**

#### **A. COMPREHENSIVE PLAN:**

1. The Future Land Use Map of the La Vista Comprehensive Plan designates this property for commercial development. This application is contingent on the approval of the proposed amendment to the Future Land Use Map of the Comprehensive Plan that would change the designation from commercial to high-density residential.

#### **B. OTHER PLANS: N/A.**

#### **C. TRAFFIC AND ACCESS:**

1. A traffic impact analysis prepared by Felsburg, Holt & Ullevig (FHU) was submitted and reviewed through the approval process for Phase 1 of the Echo Hills Apartments and the Echo Hills Assisted Living and Memory Care facilities. As a result of this study and the subdivision agreement approved by the La Vista City Council on July 10, 2020, the applicant has made the following street signal improvements at the intersection of 144<sup>th</sup> Street and Chandler Road:
  - i. Added a permissive/protected phase to the northbound left turn lane with a 4-section signal head to include a flashing yellow arrow; and
  - ii. Modification to 3-section signal heads, with a flashing yellow arrow, to all other left turning lane signal head as to be consistent with signals in the vicinity.
2. A trip generation comparison was completed by Felsburg, Holt & Ullevig (FHU) to explore the traffic generation differences between the previously approved PUD site plan and commercial development concept for Lots 3 and 4 Echo Hills Replat Four and the proposed revised PUD site plan and multi-family residential development. A memo containing this analysis, dated December 29, 2021, concludes "based on the trip generation analysis results, no significant impact is anticipated to traffic conditions with the proposed changes in land uses and quantities."
3. The trip generation comparison memo mentioned above has been reviewed by the Nebraska Department of Transportation and Sarpy County Public Works, and both have expressed no comments or concerns.
4. As part of the Echo Park Apartments phase 1 development to mitigate the potential negative impacts of increased traffic to the neighborhood, the applicant installed a speed table and pedestrian crossing on 146th Street, a speed hump on Echo Hills Drive, a fence along the east edge of Echo Hills Park along 146th Street, additional on-street parking stalls for Echo Hills

park, and an improved sidewalk connection to the park from the neighborhood.

**D. UTILITIES:**

1. The property has access to all necessary utilities.

**E. PARKING REQUIREMENTS:**

1. The minimum off-street parking stall requirements for the proposed development per Section 7.06 of the La Vista Zoning Ordinance and the number of proposed parking stalls for each lot in the development are as follows:

<u>Lot #</u>	<u>Use</u>	<u>Required Stalls</u>	<u>Provided Stalls</u>
Lot 1	Assisted Living & Memory Care	80 + 24 Employees	82
Proposed Lot 1 Echo Hills Replat Five	Multi-Family with one commercial bay with a drive-through	385	422

2. With the approval of the original PUD Site Plan, the applicant was granted a reduction in the required parking stall count for the assisted living and memory care facility and Lot 1 Echo Hills Replat Four based on historical data from the operating history of similar projects. The applicant anticipates that only 5 assisted living residents will operate vehicles, and that no memory care residents will be operating a vehicle, greatly reducing the need for parking. This reduction of parking for this facility was approved.
3. The proposed number of provided off-street parking stalls for Lot 2-4 Echo Hills Replat Four (proposed Lot 1 Echo Hills Replat Five) exceeds the minimum number of stalls required by Section 7.06 of the La Vista Zoning Ordinance.
4. Per Section 7.05.09, multi-family housing developments shall provide a minimum of 0.5 enclosed garages per unit, but these garages may count toward the total number of parking spaces required. With 281 units, this requirement for the Echo Park Apartments is to provide a minimum of 141 garage stalls. This proposal includes 153 garage stalls (88 stalls in the garage under apartment building #3, and 65 single garages under apartment buildings #1, #2, #4, and #5).

**IV. REVIEW COMMENTS:**

1. Per Section 5.15.02.04 of the La Vista Zoning Ordinance, land uses not permitted in the underlying zoning district may be allowed by City Council through a Planned Unit Development Overlay District to promote mixed-use development. The development proposal related to this application includes a coffee/shop (commercial) use

on the property which is not currently permitted in the underlying R-3 High Density Residential Zoning District, but will be permitted through the PUD ordinance if approved by City Council.

2. The applicant has requested an allowance for a reduction in the lot area minimum requirement for the R-3 High-Density Residential Zoning District from 3,000 square feet for the first four units and 1,500 square feet for each additional unit to 3,000 square feet for the first four units and 1,316 square feet for each additional unit. This represents an 11% reduction in the lot area requirement for the multi-family housing on proposed Lot 1 Echo Hills Replat Five. A formal request letter for this allowance was submitted and is attached to the staff report for the PUD application. Allowances for this lot area requirement may be granted by City Council through the Planned Unit Development process, per Section 5.15.02.04 of the La Vista Zoning Ordinance.
3. The building design for the Echo Park Apartments Building #5 is currently under review by the City's third-party Design Review Architect. This design review process must be substantially complete prior to application for building permits.
4. The landscaping plan is currently under review by the City's third-party Design Review Architect and must be approved prior to building permit issuance.
5. Through the Conditional Use Permit, limitations will be placed on the commercial or coffee shop user proposed for the 1,800 square foot space on the west side of apartment building #5, to ensure that the user is one that can regularly maintain a drive through stacking queue of 5 cars or fewer (or such amount that the City Engineer deems appropriate for the location) to ensure that vehicles in the proposed drive-through do not stack out onto the public street.
6. A draft subdivision agreement is attached. It addresses items including but not limited to: public and private improvements, maintenance of common areas, staking bonds, guarantees and performance bonds, etc.

**V. STAFF RECOMMENDATION – REPLAT:**

Staff recommends approval of the replat for Lots 2-4 Echo Hills Replat Four, being replatted as Lot 1 Echo Hills Replat Five, subject to satisfaction of all applicable requirements, including without limitation, notice, hearing, and approval of amendments to the Future Land Use Map of La Vista's Comprehensive Plan, the Official Zoning Map, the Planned Unit Development Site Plan, and the Conditional Use Permit.

**V. PLANNING COMMISSION RECOMMENDATION – REPLAT:**

The La Vista Planning Commission held a meeting on March 3, 2022 and voted unanimously to recommend approval of the replat for Lots 2-4 Echo

Hills Replat Four, being replatted as Lot 1 Echo Hills Replat Five, subject to satisfaction of all applicable requirements, including without limitation, notice, hearing, and approval of amendments to the Future Land Use Map of La Vista's Comprehensive Plan, the Official Zoning Map, the Planned Unit Development Site Plan, and the Conditional Use Permit.



**VI. ATTACHMENTS TO REPORT:**

- A. Review and response letters
- B. Preliminary Plat plan set
- C. Final Plat
- D. Subdivision Agreement


**VII. COPIES OF REPORT SENT TO:**

- A. Brett West, West Management, LLC
- B. Joe Dethlefs, Thompson, Dreessen & Dorner, Inc.
- C. Public Upon Request

Cale Brodersen  
Prepared by: Assistant Planner  
Brett J. Thompson 3/25/22  
Community Development Director Date



## Echo Hills Replat Five Area Exhibit - West Management, LLC



### Legend

■ TaxParcel

■ Proposed Replat Area



January 25, 2022

Joe Dethlefs  
Thompson, Dreessen & Dorner, Inc.  
10836 Old Mill Road  
Omaha, NE 68154

RE: Echo Hills Replat Five – Initial Review Letter

Mr. Dethlefs,

We have reviewed the documents submitted for the above-referenced application. Based on the elements for consideration set forth in the applicable sections of the Subdivision Regulations, the City has the following comments:

1. Please include phasing lines on the preliminary plat to delineate what work has been completed, what is proposed, and/or if phasing is contemplated for the remaining work, per Section 3.03.02 of La Vista's Subdivision Regulations.
2. The updated traffic impact analysis that was submitted is currently under review. This TIA will need to be reviewed by the Nebraska Department of Transportation for the intersections along 14<sup>th</sup> Street (HWY 50), and by Sarpy County Public Works for the intersections along Chandler Road.
3. A revised grading plan and Post Construction Stormwater Management Plan (PCSMP) will need to be completed for this project to encapsulate the changes in grading and stormwater runoff associated with the change in land use. Final plans and drainage study will need to be submitted through the PERMIX website at the time of building permit.

**City Hall**  
8116 Park View Blvd.  
La Vista, NE 68128-2198  
402.331.4343 P  
402.331.4375 F

**Community Development**  
8116 Park View Blvd.  
402.593.6400 P  
402.593.6445 F

**Library**  
9110 Giles Rd.  
402.537.3900 P  
402.537.3902 F

**Police**  
7701 S. 96th St.  
402.331.1582 P  
402.331.7210 F

**Public Works**  
9900 Portal Rd.  
402.331.8927 P  
402.331.1051 F

**Recreation**  
8116 Park View Blvd.  
402.331.3455 P  
402.331.0299 F

4. Please confirm that the notarization block is consistent with Section 10.01 of the Subdivision regulations. The final statement is missing from the block on the final plat.
5. Please provide financial data showing costs of all required public improvements proposed and yet to be completed.
6. The submitted, revised subdivision agreement is currently under review. We will notify you in the near future of any necessary changes.

Please resubmit 2 paper copies of the revised Preliminary and Final Plats (along with electronic copies) to the City for further review. A timeline for review by the Planning Commission and City Council will be determined based on the timing of the resubmittal and the extent to which the issues noted this review have been sufficiently addressed. If you have any questions regarding these comments, please feel free to contact me at any time.

Thank you,



Cale Brodersen, AICP  
Assistant Planner  
City of La Vista  
[cbrodersen@cityoflavista.org](mailto:cbrodersen@cityoflavista.org)  
(402) 593-6405

cc:

Brett West - West Management, LLC  
Bruce Fountain, Community Development Director – City of La Vista  
Christopher Solberg, Deputy Community Development Director – City of La Vista  
Pat Dowse, City Engineer – City of La Vista

January 27, 2022

Cale Brodersen  
City of La Vista  
8116 Park View Boulevard  
La Vista, NE 68128

RE: Echo Hills Replat Five – Initial Review Letter Response

Mr. Brodersen,

Below are responses to the comments on the Echo Hills Replat Five initial review letter dated January 25, 2022, for the proposed development at Echo Hills Replat Five. The City comments are listed below followed by our response in bold.

1. Please include phasing lines on the preliminary plat to delineate what work has been completed, what is proposed, and/or if phasing is contemplated for the remaining work, per Section 3.03.02 of La Vista's Subdivision Regulations.  
**Phasing lines have been added to the Preliminary Plat.**
2. The updated traffic impact analysis that was submitted is currently under review. This TIA will need to be reviewed by the Nebraska Department of Transportation for the intersections along 14<sup>th</sup> Street (HWY 50), and by Sarpy County Public Works for the intersections along Chandler Road.  
**TD2 acknowledges. The TIA will be reviewed by NDOT and Sarpy County Public Works.**
3. A revised grading plan and Post Construction Stormwater Management Plan (PCSM) will need to be completed for this project to encapsulate the changes in grading and stormwater runoff associated with the change in land use. Final plans and drainage study will need to be submitted through the PERMIX website at the time of building permit.  
**TD2 acknowledges. A revised grading plan and PCSMP will be submitted as part of the building permit process.**
4. Please confirm that the notarization block is consistent with Section 10.01 of the Subdivision regulations. The final statement is missing from the block on the final plat.  
**The final plat has been updated to be consistent with Section 10.01.**

5. Please provide financial data showing costs of all required public improvements proposed and yet to be completed.  
**Section 3 of the Subdivision Agreement outlines the proposed public improvements and the responsibility of payment.**
6. The submitted, revised subdivision agreement is currently under review. We will notify you in the near future of any necessary changes.  
**TD2 acknowledges.**

We appreciate the City's effort in preparing this review. We would like to continue working with the City to address any unresolved items. Please contact our office with any questions or concerns.

Respectfully submitted,

THOMPSON, DREESSEN & DORNER, INC.



Trevor Veskrna, E.I.



# ECHO HILLS REPLAT 5

LOT 1

## SARPY COUNTY, NEBRASKA



**VICINITY MAP**

1. EXISTING ZONING IS GENERAL COMMERCIAL AND HIGH DENSITY RESIDENTIAL (C-4 AND R-3 GATEWAY CORRIDOR), PROPOSED ZONING IS R-3 PUD GATEWAY CORRIDOR.
2. EXISTING AND PROPOSED CONTOURS ARE SHOWN AT 2 FT. INTERVALS.
3. WATER SHALL BE PROVIDED BY METROPOLITAN UTILITIES DISTRICT.
4. GAS SHALL BE PROVIDED BY THE BLACK HILLS ENERGY.
5. POWER SHALL BE PROVIDED FROM THE OMAHA PUBLIC POWER DISTRICT.
6. TYPICAL UTILITY EASEMENTS WILL BE DEDICATED WITH THE FINAL PLAT.
7. LOT 1 REPLAT 4 IS NOT INCLUDED IN THIS REPLAT AND IS SHOWN FOR INFORMATIONAL PURPOSES ONLY.

PROPERTY OWNER

ECHO HILLS APARTMENTS LLC  
129 N 10TH STREET UNIT 106  
LINCOLN, NE 68508  
PHONE: 402-826-9393

## SUBDIVIDER

ECHO HILLS APARTMENTS LLC  
129 N 10TH STREET UNIT 106  
LINCOLN, NE 68508  
PHONE: 402-826-9393


## ENGINEER

THOMPSON, DREESSEN & DORNER  
10836 OLD MILL ROAD  
OMAHA, NEBRASKA 68154  
PHONE: 402-732-8860

LEGAL DESCRIPTION

**LEGAL DESCRIPTION**

#### LEGEND



**TD2**  
engineering  
& surveying

thompson, dreessen & dorner, inc.  
10836 Old Mill Rd  
Omaha, NE 68154  
p.402.330.8860 www.td2co.com

Project Name

Client Name

Professional Sc

Review Date:

No.	Description	MM-DD-YY
1		
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		
21		
22		
23		
24		
25		
26		
27		
28		
29		
30		
31		
32		
33		
34		
35		
36		
37		
38		
39		
40		
41		
42		
43		
44		
45		
46		
47		
48		
49		
50		
51		
52		
53		
54		
55		
56		
57		
58		
59		
60		
61		
62		
63		
64		
65		
66		
67		
68		
69		
70		
71		
72		
73		
74		
75		
76		
77		
78		
79		
80		
81		
82		
83		
84		
85		
86		
87		
88		
89		
90		
91		
92		
93		
94		
95		
96		
97		
98		
99		
100		
101		
102		
103		
104		
105		
106		
107		
108		
109		
110		
111		
112		
113		
114		
115		
116		
117		
118		
119		
120		
121		
122		
123		
124		
125		
126		
127		
128		
129		
130		
131		
132		
133		
134		
135		
136		
137		
138		
139		
140		
141		
142		
143		
144		
145		
146		
147		
148		
149		
150		
151		
152		
153		
154		
155		
156		
157		
158		
159		
160		
161		
162		
163		
164		
165		
166		
167		
168		
169		
170		
171		
172		
173		
174		
175		
176		
177		
178		
179		
180		
181		
182		
183		
184		
185		
186		
187		
188		
189		
190		
191		
192		
193		
194		
195		
196		
197		
198		
199		
200		
201		
202		
203		
204		
205		
206		
207		
208		
209		
210		
211		
212		
213		
214		
215		
216		
217		
218		
219		
220		
221		
222		
223		
224		
225		
226		
227		
228		
229		
230		
231		
232		
233		
234		
235		
236		
237		
238		
239		
240		
241		
242		
243		
244		
245		
246		
247		
248		
249		
250		
251		
252		
253		
254		
255		
256		
257		
258		
259		
260		
261		
262		
263		
264		
265		
266		
267		
268		
269		
270		
271		
272		
273		
274		
275		
276		
277		
278		
279		
280		
281		
282		
283		
284		
285		
286		
287		
288		
289		
290		
291		
292		
293		
294		
295		
296		
297		
298		
299		
300		

Drawn By: TDV Reviewed By: JAD  
Job No.: 2142-103 Date: 02-25-22

# Preliminary Plat Grading & Erosion Control Plan

Sheet Number

## Ex. B

# ECHO HILLS REPLAT 5

LOT 1

## SARPY COUNTY, NEBRASKA



## VICINITY MAP

## NOTES

1. EXISTING ZONING IS GENERAL COMMERCIAL AND HIGH DENSITY RESIDENTIAL (R-1 AND R-3 GATEWAY CORRIDOR). PROPOSED ZONING IS R-3 PUD GATEWAY CORRIDOR.
2. EXISTING AND PROPOSED COUNTERS ARE SHOWN AT 2 FT. INTERVALS.
3. WATER SHALL BE PROVIDED BY METROPOLITAN UTILITIES DISTRICT.
4. GAS SHALL BE PROVIDED BY THE BLACK HILLS ENERGY.
5. POWER SHALL BE PROVIDED FROM THE OMAHA PUBLIC POWER DISTRICT.
6. TYPICAL UTILITY EASEMENTS WILL BE DEDICATED WITH THE FINA PLAT.
7. LOT 104 REPLAT 4 IS NOT INCLUDED IN THIS REPLAT AND IS SHOWN FOR INFORMATIONAL PURPOSES ONLY.

PROPERTY OWNER

ECHO HILLS APARTMENTS LLC  
129 N 10TH STREET UNIT 106  
LINCOLN, NE 68508

## SUBDIVIDER

**ECHO HILLS APARTMENTS LLC  
129 N 10TH STREET UNIT 106  
LINCOLN, NE 68508**

## ENGINEER

THOMPSON, DREESSEN & DORNER  
10836 OLD MILL ROAD  
OMAHA, NEBRASKA 68154  
PHONE: 402-330-8860

LEGAL DESCRIPTION

**LEGAL DESCRIPTION**

#### UTILITY LEGEND

**UTILITY LEGEND**

—○— PROPOSED SANITARY SEWER

—W— PROPOSED WATER MAIN

 PROPOSED STORM SEWER

—Δ— EXISTING STORM SEWER

—SS— EXISTING SANITARY SEWER

—W— EXISTING WATER MAIN

○ PROPOSED FIRE HYDRANT

○ PROPOSED PIV VALVE

○ EXISTING FIRE HYDRANT

**TD2**  
engineering  
& surveying

thompson, dreessen & dorner, inc.  
10836 Old Mill Rd  
Omaha, NE 68154  
p.402.330.8860 www.td2co.com

Project Name

Client Name

Page 18

#### Revision Dates

No.	Description	MM-DD-YY
1		
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		
21		
22		
23		
24		
25		
26		
27		
28		
29		
30		
31		
32		
33		
34		
35		
36		
37		
38		
39		
40		
41		
42		
43		
44		
45		
46		
47		
48		
49		
50		
51		
52		
53		
54		
55		
56		
57		
58		
59		
60		
61		
62		
63		
64		
65		
66		
67		
68		
69		
70		
71		
72		
73		
74		
75		
76		
77		
78		
79		
80		
81		
82		
83		
84		
85		
86		
87		
88		
89		
90		
91		
92		
93		
94		
95		
96		
97		
98		
99		
100		

Drawn By: TDV Reviewed By: JAD  
Job No.: 2142-103 Date: 02-25-22

Sheet Title

### Shoot Number

### Ex. C

Site plan for the Echo Hills Subdivision, showing property lots, roads, and utility infrastructure. The plan includes labels for 'ECHO HILLS REPLAT', 'LOT 1 ECHO HILLS', 'LOT 4', 'LOT 5', 'LOT 6', 'LOT 7', 'LOT 8', 'LOT 18', 'LOT 34', 'LOT 35', 'LOT 5 ECHO HILLS', and 'LOT 1 REPLAT 5 (8.649 AC) PROPOSED R-3 (PUD) GATEWAY CORRIDOR DISTRICT'. It also shows 'ECHO HILLS REPLAT' and 'ECHO HILLS' labels. Roads include '14th STREET (Right-of-Way - Varied)', 'SOUTH HIGHWAY 50 (PUBLIC RIGHT-OF-WAY)', 'CHANDLER ROAD (PUBLIC RIGHT-OF-WAY)', and 'CONCRETE'. Utilities include 8" PVC, 12" HDPE/PVC, 18" HDPE/PVC, 24" HDPE/PVC, 30" HDPE/PVC, 30" RCP, and 8" SS. A north arrow is located in the bottom right corner.

# ECHO HILLS REPLAT 5

LOT 1

## SARPY COUNTY, NEBRASKA



## VICINITY MAP

## NOTES

1. EXISTING ZONING IS GENERAL COMMERCIAL AND HIGH DENSITY RESIDENTIAL (C-1 AND R-3 GATEWAY CORRIDOR), PROPOSED ZONING IS R-3 PUD GATEWAY CORRIDOR.
2. EXISTING AND PROPOSED CONTOURS ARE SHOWN AT 2 FT. INTERVALS.
3. WATER SHALL BE PROVIDED BY METROPOLITAN UTILITIES DISTRICT.
4. GAS SHALL BE PROVIDED BY THE BLACK HILLS ENERGY.
5. POWER SHALL BE PROVIDED FROM THE OMAHA PUBLIC POWER DISTRICT.
6. TYPICAL UTILITY EASEMENTS WILL BE DEDICATED WITH THE FINAL PLAT.
7. LOT #4 REPLAT 4 IS NOT INCLUDED IN THIS REPLAT AND IS SHOWN FOR INFORMATIONAL PURPOSES ONLY.

**PROPERTY OWNER**

ECHO HILLS APARTMENTS LLC  
129 N 10TH STREET UNIT 106  
LINCOLN, NE 68508

## SUBDIVIDER

ECHO HILLS APARTMENTS LLC  
129 N 10TH STREET UNIT 106  
LINCOLN, NE 68508  
PHONE: 402-826-9393

## ENGINEER

THOMPSON, DREESSEN & DORNER  
10836 OLD MILL ROAD  
OMAHA, NEBRASKA 68154  
PHONE: 402-330-8860

LEGAL DESCRIPTION

**LEGAL DESCRIPTION**

## LEGEND

The legend consists of four square icons with corresponding labels:

- PROPOSED 7" P.C.C. PAVEMENT**: Represented by a solid black square.
- PROPOSED 4" P.C.C. SIDEWALK, 5" P.C.C. IN RIGHT OF WAY**: Represented by a square with a diagonal hatching pattern.
- PROPOSED SIDEWALK EASEMENT**: Represented by a square with horizontal hatching.
- EXISTING PAVEMENT**: Represented by a square with a dotted pattern.

**TD2**  
engineering  
& surveying

thompson, dreessen & dorner, inc.  
10836 Old Mill Rd  
Omaha, NE 68154  
p.402.330.8860 www.td2co.com

Project Name

Client Name  
**Echo Hills  
Apartments LLC**

Professional Se

### Revision Dates

No.	Description	MM-DD-YY
1		
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		
21		
22		
23		
24		
25		
26		
27		
28		
29		
30		
31		
32		
33		
34		
35		
36		
37		
38		
39		
40		
41		
42		
43		
44		
45		
46		
47		
48		
49		
50		
51		
52		
53		
54		
55		
56		
57		
58		
59		
60		
61		
62		
63		
64		
65		
66		
67		
68		
69		
70		
71		
72		
73		
74		
75		
76		
77		
78		
79		
80		
81		
82		
83		
84		
85		
86		
87		
88		
89		
90		
91		
92		
93		
94		
95		
96		
97		
98		
99		
100		

Drawn By: TDV Reviewed By: JAD  
Job No.: 2142-103 Date: 02-25-22

Sheet Title

### Shoot Number

## Ex. D

## ECHO HILLS REPLAT 5

LOT 1

**TD2**  
engineering  
& surveying

thompson, dreessen & dorner, inc.  
10836 Old Mill Rd  
Omaha, NE 68154  
p.402.330.8860 www.td2co.com

Project Name



**VICINITY MAP**

---

1. EXISTING ZONING IS GENERAL COMMERCIAL AND HIGH DENSITY RESIDENTIAL (C-1 AND C-2, GROWTH CORRIDOR). PROPOSED ZONING IS R-3, PLAT GATEWAY CORRIDOR.
2. EXISTING AND PROPOSED CONTOURS ARE SHOWN AT 2 FT. INTERVALS.
3. WATER SHALL BE PROVIDED BY METROPOLITAN UTILITIES DISTRICT.
4. GAS SHALL BE PROVIDED BY THE BLACK HILLS ENERGY.
5. POWER SHALL BE PROVIDED FROM THE OMAHA PUBLIC POWER DISTRICT.
6. TYPICAL UTILITY EASEMENTS WILL BE DEDICATED WITH THE FINAL PLAT.
7. LOT 1, REPLAY 4 IS NOT INCLUDED IN THIS REPLAY AND IS SHOWN FOR INFORMATIONAL PURPOSES ONLY.

PROPERTY OWNER

ECHO HILLS APARTMENTS LLC  
129 N 10TH STREET UNIT 106  
LINCOLN, NE 68508  
PHONE: 402-826-9393

## SUBDIVIDE

ECHO HILLS APARTMENTS LLC  
129 N 10TH STREET UNIT 106  
LINCOLN, NE 68508  
PHONE: 402-826-9393

ENGINEER

THOMPSON, DREESSEN & DORNER  
10836 OLD MILL ROAD  
OMAHA, NEBRASKA 68154  
PHONE: 402-330-8860

LEGAL DESCRIPTION

LOT 1, ECHO HILLS REPLAT 5, BEING A REPLATTING OF LOTS  
1, 2, 3, AND 4, ECHO HILLS REPLAT 4, A SUBDIVISION IN SARPY  
COUNTY, NEBRASKA.

Drawn By: TDV Reviewed By: JAD  
Job No.: 2142-103 Date: 02-25-22

Sheet Title

Sheet Number \_\_\_\_\_

## Ex. E





**SUBDIVISION AGREEMENT**  
**Lot 1 Replat 4 & Lot 1 Replat 5, Echo Hills**  
**144th and Chandler Road**  
**R-3, High Density Residential PUD GWC**  
**(Private Financing)**

THIS SUBDIVISION AGREEMENT (the "Agreement") is made this \_\_\_\_ day of \_\_\_\_\_, 2022, by and between ECHO HILLS APARTMENTS LLC and ECHO HILLS ALMC LLC, two Nebraska limited liability companies authorized to do business in Nebraska, (hereinafter referred to as "Subdivider"), and the CITY OF LA VISTA, a Municipal Corporation in the State of Nebraska (hereinafter referred to as "City"). Subdivider and the City are sometimes referred to herein individually as a "Party" and collectively as the "Parties."

WITNESSETH:

WHEREAS, Subdivider is the owner of the property to be platted or replatted as Lot 1, Echo Hills Replat 4 and Lot 1, Echo Hills Replat 5, a subdivision, as surveyed, platted and recorded in Sarpy County, Nebraska ("Lot 1 Replat 4, Lot 1 Replat 5") as is more particularly shown on the Final Plat (the "Plat") attached hereto as Exhibit "A," as finally approved by the City Council, and which is located outside of the corporate limits of the City but within the City's zoning and platting jurisdiction ("Property");

WHEREAS, Subdivider desires to own, develop and operate Lot 1 Replat 4 in a unified, compatible manner as an 80 unit assisted living and memory care facility comprised of a single building containing 60 assisted living units and 20 memory care units. And, whereas, the Subdivider desires to own, develop and operate Lot 1 Replat 5 in a unified compatible manner as a 281 unit multi-family residential housing project comprised of five separate residential apartment buildings, a total of 156 detached and attached fully enclosed single-vehicle parking garages, all as presented to the City Council with the Subdivider's request for approval of the Plat, PUD Plan and Conditional Use Permit, and as finally approved;

WHEREAS, Subdivider has agreed to meet all applicable conditions and requirements of the City's platting, development and zoning laws, regulations and requirements, including without limitation those that are set forth in the City's Zoning Ordinance, Subdivision Regulations, PUD Plan, Conditional Use Permit, Building Code and this Agreement;

WHEREAS, Subdivider has requested the City approve the Plat and approve the rezoning of Lot 1 Replat 5 to R-3, High Density Residential PUD, with the Gateway Corridor Overlay (GWC).

WHEREAS, in order to develop Lot 1 Replat 4 and Lot 1 Replat 5 in the way it wishes, Subdivider must grade, create, construct and maintain certain topographic and surface conditions and provide for surface water detention within the Subdivision in accordance with applicable requirements;

WHEREAS, Subdivider has requested that the City approve the Plat and approve the connection of the Subdivision to existing sanitary sewer and storm drainage systems;

WHEREAS, Subdivider will build all public improvements and private infrastructure improvements identified in "Exhibits "C", "G" and "H", or as otherwise described in this Agreement;

WHEREAS, Subdivider requested approval of the Plat, subject to the following provisions of the City of La Vista Zoning Ordinance: Section 5.08 (pertaining to R-3 High Density Residential District), Section 5.15 (pertaining to PUD), Section 5.17.06 (Gateway Corridor Overlay District), and Article 6 (pertaining to Conditional Use Permits), and has agreed to meet all conditions of development and other requirements of said zoning set forth in this Agreement; and

WHEREAS, the Parties wish to agree upon various matters pertaining to the construction of the private infrastructure and public improvements within the Subdivision or serving the Subdivision and other matters pertaining to the development of the Subdivision and health, safety and welfare of the City, their inhabitants and the public.

NOW, THEREFORE, IT IS AGREED as follows:

1. Definitions

Unless a contrary intent is clearly indicated herein, the following words and phrases shall have the following meanings, regardless of whether or not capitalized:

- A. "Agreement" shall mean this document entitled "Subdivision Agreement" and all Exhibits hereto (see Section 13 "Recitals/Exhibits Summary").
- B. "Conditional Use Permit" shall refer to that certain conditional use permit which is attached hereto as Exhibit "B", as finally approved by the City Council and executed by the parties.
- C. The "construction cost" of an improvement shall mean the amount paid to the contractor, utility or entity installing the improvement or performing the work, together with all other direct labor and material costs incorporated into the construction of the improvement, and net of refunds, reimbursements and offsets thereto.
- D. The "cost" or "entire cost" of a type of improvement shall be deemed to include all construction costs, engineering fees, attorneys' fees, testing expenses, publication costs, financing costs, and other costs of achieving completion, acceptance and financing of the project or work and miscellaneous costs.
- E. "Detention Basin" or "Storm Water Detention Basin" shall mean a permanent structure to serve as temporary water holding basin, whether above or below ground, to be constructed at the locations shown in the Post Construction Storm Water Management Plan attached as Exhibit "G", or such alternative or substitute locations and accompanying plans and specifications as the City may approve in advance in writing.
- F. "Improvements" or "Infrastructure" shall mean, to the extent located within the Subdivision or required herein for development of the Subdivision, or pertaining to Subdivision entrances, any and all facilities constructed or otherwise implemented for the purpose of providing access or services of any type or description to or from the Subdivision or serving facilities or properties within or serving the Subdivision, including but not limited to, ingress and egress to and from the Sub-division, and construction of paving, enhancements or reconstruction of existing paving and traffic signalization in conjunction therewith, and construction of storm sewers, sanitary sewers, including outfall sewer, and access thereto, drain-age and drainage retention, culverting, street lighting, and any other item of infra-structure, together with utility systems and easements for any improvements, or the maintenance, replacement, or repair thereof, where required.

G. "Land Utilization and Preparation Costs" shall include, but not be limited to, all costs pertaining to, or arising out of, determination of feasibility, acquisition, reclamation, preparation, enhancement and/or utilization of land within Echo Hills, and all engineering, legal, financing and contracted or other services related thereto or to the following:

- (1) Soil and water tests, topographic surveys, geotechnical investigation and environmental studies and drainage studies, water drainage ways and surface water retention and/or detention basins or facilities, surveying, staking and testing;
- (2) Platting (preliminary and final), and including replatting;
- (3) Excavation, filling, compaction, stabilization and testing thereof;
- (4) Grading;
- (5) Erosion and silt control, including installation and removal thereof;
- (6) Environmental studies and permits required by Corps of Engineers or other governmental agencies having jurisdiction in the matter and costs of compliance with the terms of such permits and requirements thereof;
- (7) Buffer zones and areas to be landscaped or beautified, including trees and other plantings therein or therefor;
- (8) Traffic and other required studies;
- (9) Such other costs incurred to utilize and/or prepare land located within Echo Hills to a City approved final grade, elevation, drainage control and soil condition ready for installation or construction of the Private Improvements and the Public Improvements authorized by this Agreement or to improve, enhance or beautify land.

H. "Plat" or "the Plat," unless a contrary intent is indicated, shall mean the final plat attached as Exhibit "A", as finally approved by the City Council.

I. "PUD Plan" shall mean the Planned Unit Development Plan for the Subdivision, including, but not limited to, the Planned Unit Development Site Plan and Landscaping Plan attached as Exhibits "D" and "E", as finally approved by the City.

J. "Subdivider's Engineer" shall mean TD2 Engineering & Surveying, which shall be the principal contact entity with the City in engineering matters.

K. "Subdivision" or "Echo Hills" shall mean the approximately 12.43 acres of land described in Exhibit "A" hereto.

L. "Subdivider" shall mean Echo Hills Apartments, LLC, a Nebraska limited liability company, and Echo Hills Almc, LLC, a Nebraska limited liability company.

M. "District" shall mean Sanitary and Improvement District No. 68 of Sarpy County Nebraska.

N. "Public Improvements" shall mean those improvements described in Subsections 2A, 2B, 2C, 2D, and 6.

O. "Private Improvements" shall mean all improvements described in this Agreement, other than Public Improvements, including without limitation those improvements described in Subsections 2E, 2F, and 2G.

2      Construction/Installation of Improvements Authorized.

The Parties, in addition to any other improvements specified by this Agreement, shall construct or install, or cause to be constructed or installed, the following types of improvements upon the property located within or immediately adjacent to the boundaries of the Subdivision and necessary water, sanitary sewer, and surface water drainage to or from existing or planned facilities as follows, and no funds, assets or other resources or credit of the District or the City shall be expended, loaned, applied or otherwise used by or for the benefit of the Subdivision, Subdivider or any Improvements, or any fee, cost or expense described or related to any matter described in this Agreement, except as expressly authorized in advance by the City in writing:

- A. Pedestrian Crossing and Speed Table on 146<sup>th</sup> Street The subdivider, at its cost, shall install or cause to install a speed table and pedestrian crossing on 146<sup>th</sup> Street as located on attached "Exhibit "D".
- B. Speed Hump on Echo Hills Drive The subdivider, at its cost, shall install or cause to install a speed bump on Echo Hills Drive as located on attached "Exhibit "D".
- C. Fence and Pedestrian Sidewalk Extension Along East Edge of Echo Hills Park The subdivider, at its cost, shall install or cause to install a four foot high metal fence (fence type to be approved by the City) and extend the pedestrian sidewalk along the east edge of Echo Hills Park as located on attached "Exhibit "D".
- D. Signalization of 144<sup>th</sup> & Chandler Road. The subdivider, at its cost, shall:
  - (1) Add or cause to add a permissive/protected phase to the northbound left turn lane with a 4-section signal head to include a flashing yellow arrow, and the modification to 3-section signal heads, with a flashing yellow arrow, to all other left turning lane signal head as to be consistent with signals in the vicinity; and
- E. Storm Water Detention.
  - (1) A drainage study for the Subdivision based on development of Lot 1 Echo Hills Replat 4 and Lot 1 Echo Hills Replat 5 has been completed and the executive summary is attached hereto as Exhibit "F" ("Drainage Study"), the results of which include projections regarding storm water drainage from the Subdivision after it is developed, including construction of storm water detention facilities within the Subdivision ("Projected Post-Development Drainage"). Subdivider certifies that, to the best of its knowledge, the Drainage Study is current, accurate and complete and that actual drainage from the Subdivision during and after development of the Subdivision will not exceed Projected Post-Development Drainage; provided, however, that Subdivider shall not be responsible for increased drainage from the Subdivision caused by improvements upstream of the Subdivision that are initiated and completed after the Drainage Study was completed, are beyond the control of Subdivider and materially increase the amount of storm water drainage flowing into the Sub- division. Subdivider, at its cost, agrees to construct no later than the date(s) specified in or determined in accordance with Subsection 1 l(A)(1) the storm water detention basins and associated

storm sewer piping and related improvements in accordance with the Utility Plan attached hereto as Exhibit "H" and the Post Construction Storm Water Management Plan attached hereto as Exhibit "G". Subdivider, subject to any applicable permit, agreement or other requirement, shall connect to the existing storm sewer system. Storm water detention facilities and improvements are a Land Utilization and Preparation Cost within the meaning of Section 1 hereof and shall be constructed at Subdivider's expense. If actual drainage from the Subdivision during or after development exceeds Projected Post-Development Drainage, Subdivider, at its cost, shall take such additional actions within the Subdivision as are necessary or appropriate to reduce actual drainage from the Subdivision to the Projected Post- Development Drainage levels, to the satisfaction of the City Engineer. Provided, however, that Subdivider shall not be responsible for increased drainage from the Subdivision caused by improvements upstream of the Subdivision that are initiated and completed after the Drainage Study was completed, are beyond the control of Subdivider and materially increase the amount of storm water drainage flowing into the Subdivision. Prior to issuance of any building permit, Subdivider shall adopt a Post Construction Storm Water Management Plan governing perpetual operation, maintenance and repair of storm water detention basins and facilities in the Subdivision specified in the Utility Plan attached hereto as Exhibit "H" and the and the Post Construction Storm Water Management Plan attached hereto as Exhibit "G", which Post Construction Storm Water Management Plan shall be in form and content attached hereto in Exhibit "G," subject to such modifications as required by the City Administrator in consultation with the City Engineer. Subdivider at its cost shall maintain and repair all storm water detention facilities and appurtenances constructed by Subdivider within the Subdivision, which shall be Private Improvements.

- (2) All work and improvements required of Subdivider in this Subsection 2D, and related designs, contracts, plans and documents, shall be subject to prior review and approval of the City Engineer.
- (3) Watershed Management Fees: The Subdivider shall make payment to City for Watershed Fees. This fee for the Property (example shown below this paragraph) shall be computed in accordance with applicable provisions of the Master Fee Schedule set forth in the Master Fee Ordinance, as amended from time to time. Payment must be made to City's Permits & Inspections Division before a building permit will be issued to construct improvements on any lot and before the commencement of construction of any such improvements. Payment shall be based on the City's adopted fee rate that is in effect at the time the payment is made.

Lot 1 Replat 4 - 3.81 AC @ \$4,095/AC	\$15,601.95
Lot 2 Replat 4 - 5.77AC @ \$4,095/AC	\$23,628.15
Lot 1 Replat 5 - 2.88 AC @ \$4,302/AC	\$12,389.76
(Excluding Lot 2 Replat 4)	
TOTAL	\$51,619.86

The foretasted fee of \$4,302 per acre of High-Density Multi-Family Residential is the rate now in effect and is subject to increase. The rate in effect at time of building permit application will be the rate paid. Of the \$51,619.86 total, \$39,230.10 was paid in relation to Lot 1 Replat 4 and Lot 2 Replat 4 when building permits were obtained for the Echo Hills Assisted Living and Memory Care facility and the Echo Hills Apartments buildings 1-4. The watershed management fee at the time those fees were paid was \$4,095 per acre.

F. Private Storm Sewer. The Subdivider at its cost shall cause the private portion of the storm sewer system (shown in the Utility Plan attached as Exhibit "H", to be constructed, including storm sewers, inlets, manholes, junction boxes, flared end sections and other related appurtenances to be constructed in private drives or routes in the Subdivision, including those segments functioning as a transporter of storm water to points within or outside the Subdivision, as shown in the Utility Plan attached as Exhibit "H", all of which shall be Private Improvements.

G. Sanitary Sewer. The Subdivider at its cost shall install all sanitary sewers in accordance with the Utility Plan attached hereto as Exhibit "H"; and which sanitary sewers shall be Private Improvements. Subdivider, subject to written agreement of the District and City, shall connect such sewer lines to the existing public sewer line which was installed by the District pursuant to that certain Perpetual Easement, recorded June 19, 1979 at Book 52, Page 386 of the miscellaneous records of the Sarpy County Register of Deeds, and shall pay as a condition of building permit issuance all applicable connection fees at the rates in effect at the time. The Subdivider shall enter into a Sewer Connection Agreement with the City in form and content attached hereto as Exhibit "J," subject to the final approval of City Engineer.

The exact design, location and dimensions of and detailed plans and specifications for each of the above described Public Improvements or Private Improvements, are subject to prior approval by the City in advance of award of contract for construction or acquisition. Not in limitation of the foregoing sentence, any preliminary plans referenced in this Agreement shall be subject to additions, subtractions, modifications, and final approval to the satisfaction of the City Engineer.

### 3. Allocation of Cost of Improvements

Subdivider and City, except as otherwise provided by this Agreement, agree that the cost of all improvements constructed by the Subdivider within or serving the Subdivision as authorized by Section 2, supra, or elsewhere in this Agreement shall be defrayed as follows:

- (1) Pedestrian Crossing and Speed Table on 146<sup>th</sup> Street One hundred percent (100%) of the cost of the speed table and pedestrian crossing shall be paid by the subdivider at its sole cost and expense.
- (2) Speed Hump on Echo Hills Drive One hundred percent (100%) of the cost of the speed bump and shall be paid by the subdivider at its sole cost and expense.
- (3) Fence and Pedestrian Sidewalk Extension Along East Edge of Echo Hills Park One hundred percent (100%) of the cost of the fence and pedestrian sidewalk extension along the east edge of Echo Hills Park shall be paid by the subdivider at its sole cost and expense.
- (4) Signalization of 144th Street & Chandler Road. One hundred percent (100%) of the cost of the signal improvements shall be paid by the subdivider at its sole cost and expense.
- (5) Storm Sewer. One hundred percent (100%) of the cost of all storm sewers constructed

within or serving the Subdivision, including manholes, inlets and other appurtenances, as shown in the Utility Plan attached as Exhibit "H", shall be paid solely by Subdivider.

- (6) Sanitary Sewer. One hundred percent (100%) of the cost of all sanitary sewers constructed by Subdivider, within or serving the Subdivision, including manholes and other appurtenances, as shown in the Utility Plan attached as Exhibit "H", shall be paid solely by Subdivider.
- (7) Water and Electrical. All costs of causing the installation of water and electrical distribution systems and the operation, maintenance and upkeep thereof within the Subdivision, including any contract charges, shall be paid by Subdivider or the utility provider.
- (8) Other Improvements. All costs of all other work or improvements, including, but not limited to, grading, landscaping, wetlands mitigation, and extension, distribution or location of gas or other utilities, telephone or other communications or services to, on, in, over, under, within or with respect to the Subdivision, and the installation, construction, acquisition, operating or maintenance costs thereof, as applicable, shall be paid by Subdivider, and no part thereof shall be the responsibility or at the expense of the City.

#### 4. General Agreements of Subdivider

Subdivider, with respect to work and Improvements described in this Agreement, agrees that:

- A. Compliance with City Construction Requirements. Subdivider, in addition to any other requirements of applicable law or regulations, will abide by and incorporate into all contracts for Public Improvements to be constructed by Subdivider under this Agreement, the provisions required by the regulations and standards of the City and Sarpy County pertaining to construction of such Public Improvements in Subdivisions or within street right-of-way, and testing procedures therefore; provided, however, if there is any conflict or ambiguity between or among any such regulations or standards, the higher standard or quality shall control. All plans, specifications and contracts for such proposed improvements and proposed maintenance agreements for said Public Improvements shall be submitted to the City for review and approval prior to commencement of the work.
- B. Preconstruction Requirements. Prior to recording of the Plat, Subdivider will (i) in addition to any bonds required by any other provision of this Agreement, present to the City Administrator for the benefit of the City binding bonds or letters of credit in an amount of 110% of the total estimated costs of the Public Improvements to be constructed by Subdivider under this Agreement, in form and content satisfactory to the City Administrator, or (ii) complete said improvements and provide as-constructed records, certificates of completion and other required documentation, to the satisfaction of the City Engineer. If the Subdivider provides bonds pursuant to subsection (i) of the foregoing sentence, the City, upon Subdivider completing the Public Improvements, shall promptly release such bonds to the Subdivider at such time as the Subdivider's Engineer provides as-constructed records, certificates of completion of said work and improvements and other required documentation, to the satisfaction of the City Engineer.
- C. Administration. As regards to this Agreement and its implementation:

- (1) No separate administrative entity or joint venture, among the Parties, is deemed created by virtue of this Agreement.
- (2) The administration of this Agreement shall be through the offices of the undersigned officers, or their designees, for their respective entities.

D Remedies. In addition to whatever rights of enforcement of the terms hereof are herein granted to any Party, each Party may avail itself of all other remedies it may have to enforce the terms hereof at law or equity. By way of specification and not by way of limitation, each of the Parties expressly reserves the right to specifically enforce full compliance of the terms and conditions of this Agreement by mandatory or prohibitory injunction.

E Covenants, Etc. All covenants and agreements of Subdivider set forth in this Agreement shall constitute covenants running with the land and shall be binding on Subdivider and all successors and assigns of Subdivider. The City shall have the right, but not the obligation, to enforce any and all such covenants.

F. In the event the Subdivider records the Plat and, before commencing any improvements within or for the benefit of the Subdivision, Subdivider decides not to develop the Subdivision, the City and Subdivider shall take all actions necessary to vacate the Plat, and the PUD Plan, Agreement and Conditional Use Permit shall be null and void, and any letters of credit provided by Subdivider pursuant to this Agreement shall be promptly released by the City and returned to Subdivider upon vacation of the Plat.

G. Non-Discrimination. In the performance of this contract, neither the Subdivider nor the City shall discriminate against any parties or persons on account of race, national origin, sex, age, disability, political or religious affiliations in violation of federal and state laws or local ordinances.

H. The Subdivider agrees to cooperate and use all reasonable good faith efforts to complete any and all improvements and/or work required of it hereunder in a timely and orderly manner so as not to delay recording of the Plat, receipt of building permits, development of the Subdivision, or obtaining of certificates of occupancy.

## 5. Construction Standards and Procedures

Subdivider, in addition to and not in limitation of any other provisions of this Agreement or applicable law or regulations, further agrees that:

A. City Approvals. All Public Improvements will be constructed in strict accordance with contracts, plans and specifications and locations approved in advance in writing by City's Engineer and in strict accordance with the City's policies and minimum standards and requirements of construction and testing procedures therefore, and directions of City Engineer, and that upon completion of construction thereof, Subdivider shall furnish to City a certificate from its consulting engineer so certifying. All Private Improvements will be built in accordance with this Agreement and applicable requirements of the City building code or other applicable laws or regulations.

B. Testing. Subdivider shall cause appropriate testing of materials and work finished in respect to the construction of Public Improvements and shall furnish City's engineers with copies of test results. City's engineers may order additional paving core tests, sewer televising or other tests, the cost of which shall be paid by Subdivider to the party performing the testing

procedures, which additional testing costs shall also be a cost of the Public Improvement. Neither the Subdivider nor any other party shall be entitled to rely upon any inspections made by the City for any purpose whatsoever. The sole responsibility for proper inspection and certification as to completion remains with the Subdivider and its engineers.

- C. Construction Record Drawings. Subdivider shall cause "Construction Record Drawings", in reproducible form, and specifications for all Public Improvements that Subdivider shall have heretofore or hereafter constructed within the area to be developed to be furnished to City, in triplicate, promptly and without cost to the City. All such plans shall be submitted on reproducible mylar, except where the City agrees otherwise. The engineering costs attributable to the production of said "Construction Record Drawings" shall be an engineering fee within the meaning of Subsection 1-D, supra. Subdivider shall, prior to the Subdivider's solicitation of bids for any Public Improvement within the area to be developed, require Subdivider's Engineers to file with the City said Engineers' separate written assurance and agreement that said "Construction Record Drawings" will be prepared and filed with the City upon the completion of each Public Improvement.
- D. Compliance with Law. All Public Improvements shall comply with all applicable federal and state and County laws and regulations in general and with all applicable ordinances and regulations of the City in reference to construction, use, operation, and maintenance; provided, however, if there is any conflict or ambiguity between or among any such laws and regulations, the higher standard or quality shall control.
- E. Compliance with City Engineer Determinations. In the event that City's Engineers determine that there is anything in the construction, use, maintenance or operation of any Public Improvements which will, in the opinion of City's Engineers, be detrimental to any other improvement or utility constructed or to be constructed in the same right-of-way or easement, Subdivider will, on notice thereof, promptly cause its engineers to jointly review and evaluate the problem with City's engineer and formulate a plan for corrective action acceptable to the City Engineer and Subdivider which shall be implemented by Subdivider at Subdivider's cost.
- F. Bonds. Subdivider, in addition to any bonds or letters of credit required by any other provision of this Agreement, shall require each contractor performing work on Public Improvements on behalf of the Subdivider to furnish a performance and maintenance bond, and to warrant the work against any defects for a minimum of two years after completion, with Subdivider and City as joint and several obligees thereon, which bond and warranty shall be subject to the City approval as to surety, form and terms.
- G. Easements. Any easements required from Subdivider for Public Improvements hereunder by the City or its designee shall be provided at no cost to the City or its designee.

6. Sidewalks. Subdivider, at its sole cost and at no cost to the City, shall install or cause to be installed sidewalks along the south side of Echo Hills Drive adjacent to Lot 1 Replat 4 and proposed Lot 1 Replat 5, the east side of 146th Street adjacent to proposed Lot 1 Replat 5, the north side of Chandler Road adjacent to proposed Lot 1 Replat 5, and a segment along the west side of 146<sup>th</sup> street providing safer access to Echo Hills Park by the time Subdivider has completed 75% of the planned residential units in the project or at such earlier time as they are warranted as determined in the sole discretion of the City Engineer. Such sidewalks shall be constructed at Subdivider's expense. All sidewalks, whenever installed, shall be constructed in

accordance with the City sidewalk regulations and policies as they may from time to time exist, and shall be maintained at Subdivider's expense. Sidewalks adjacent to Lot 1 Replat 5 will be completed with the development of that lot.

7. Parking. The Subdivider will provide cross access parking easements between Lots 1 Replat 4 and Lot 1 Replat 5 of this subdivision.

8. Maintenance of Improvements. In addition to any other maintenance required of Subdivider pursuant to this Agreement or applicable laws or regulations, Subdivider shall continuously and permanently maintain and keep in good repair, and reconstruct or replace if required of Subdivider herein or by applicable agreements, laws, rules or regulations, all Private Improvements Subdivider constructs or makes or causes to be constructed or made with respect to development of the Subdivision, including, but not limited to landscaping. Not in limitation of any of the foregoing, all landscaping within the Subdivision shall be warranted by the landscape contractor for at least two growing seasons, and any replacement, repair or reconstruction shall be of equal or better maturity, type, quality and quantity, regardless whether or not the replacement, repair or reconstruction occurs within or after an applicable warranty period.

9. Sewer Connections. Before any connection from any premises to the sanitary sewer system of the District may be made, a permit shall be obtained for said premises and its connection from the proper department of the City, which permit shall be obtainable on the same terms, conditions, and requirements of the City applicable from time to time to permit property outside the City to connect to the sewer system of the City; it being expressly understood that the City reserves the right to collect all connection charges and fees as required by City ordinances or rules now or hereafter in force; all such connections shall comply with minimum standards prescribed by the City.

10. Tract Sewer Connection Fees. Developer agrees that the terms and conditions for the benefit of the City that are contained in the Subdivision Agreement, by and between Echo Hills Apartments LLC, a Nebraska Limited Liability Company authorized to do business in Nebraska, Echo Hills Almc LLC, a Nebraska Limited Liability Company authorized to do business in Nebraska, the City of La Vista, a Municipal Corporation in the State of Nebraska, and Sanitary Improvement District No. 68 of Sarpy County, Nebraska, dated \_\_\_\_\_, and the separate Sewer Connection Agreement referred to within Exhibit "I" as pertaining to the sanitary sewer system, shall be incorporated into this Agreement to the same extent as if fully set forth herein and equally applicable to the private sanitary sewer provided for herein and enforceable by City in respect thereto to the same extent as though the private sewer had originally been incorporated and made a part of said agreements. Tract sanitary sewer connection fees shall be due and payable to the City in the following amounts prior to the issuance of a building permit pertaining to each lot:

Lot 1, Replat 4 , R-3 - High Density Residential	80 UNITS @ \$1,064/UNIT	\$ 85,120.00
Lot 2, Replat 4, R-3 - High Density Residential	210 UNITS @ \$1,064/UNIT	\$ 223,440.00
Lot 1, Replat 5, R-3 – High Density Residential (Excluding Lot 2, Replat 4)	71 UNITS @ \$1,117/UNIT	\$ 79,307.00
	<b>TOTAL</b>	<b>\$ 387,867.00</b>

The aforesated fee of \$ 1,117 per unit is the rate now in effect and is subject to increase. The rate in effect at time of connection to the sanitary sewer system will be the rate paid. Sewer connection fees in the amount of \$308,560.00 for Lot 1 Echo Hills Replat Four and Lot 2 Echo Hills Replat Four were paid when building permits were issued for the development of these lots. The remaining \$79,307.00 (or the actual fee in effect at time of connection) for the

additional 71 units must be paid prior to issuance of building permits.

11. City Right of Disconnection. Notwithstanding any other provisions of this Agreement, City retains the right to disconnect the sanitary sewer of any industry, or other sewer user within the area to be developed, which is connected or discharging into the sanitary sewer system in violation of any applicable ordinances, statute, rule, or regulation.

12. Compliance with City Regulations, Etc. The Subdivider, without limiting any other provision of this Agreement, expressly agrees that it is and shall be:

- A. Bound by and to any provisions of any ordinances, rules and regulations as existing or hereafter made and adopted by the City applicable to sanitary and improvement districts whose sewers connect directly or indirectly with or into sewers or sewage systems of the City; and
- B. Bound by any terms and provisions which by ordinance, resolution, or rule exists or which the City shall hereafter adopt or provide as being applicable to or required in contracts with sanitary and improvement districts or in order to permit or continue the discharge of any sewage from a sanitary and improvement district to flow into or through any part of the sewer or sewage system of the City or sewer within its zoning or health jurisdiction.
- C. Bound by all terms and provisions of the Sewer Connection Agreement which is attached hereto as Exhibit "I" subject to the final approval of the City Engineer, and shall be executed in conjunction with this Agreement.

13. Additional Special Covenants and Agreements. Subdivider further covenants and agrees as follows:

- A. Storm Water Detention. In regards to storm water detention facilities:
  - (1) Subdivider's construction of storm water detention basins and facilities within the Subdivision shall be in accordance with the Utility Plan attached as Exhibit "H" and the Post Construction Storm Water Management Plan attached as Exhibit "G". Construction of storm water detention basins and facilities within Lot 1 Replat 5 shall be staged in accordance with the staged construction of buildings by Subdivider and shall be completed as necessary to handle the storm water associated with the developed portions of Lot 1 Echo Hills Replat 4 and Lot 1 Echo Hills Replat 5, which staging and schedule for construction and completion of storm water detention basins and facilities shall be subject to approval of the City Engineer before any building permit is issued for any building within the Subdivision.
  - (2) Any change of a location of a detention basin from that shown in the Post Construction Storm Water Management Plan attached as Exhibit "G" shall require approval of the City Engineer, as will any relocation of the basin from its City approved location.
  - (3) The detention basins shall be on private property. Subdivider at its cost shall be responsible for construction and continuous and permanent maintenance and repair of all detention basins and facilities located within the Subdivision.
  - (4) The City shall have an easement for access to all detention basins, as may be relocated or redesigned from time to time in accordance with this Section 11,

for inspection and any follow up, in the City's sole discretion, as is set forth in the Post Construction Storm Water Management Plan Maintenance Agreement and Easement attached as Exhibit "J", which Subdivider shall record with the Sarpy County Register of Deeds.

(5) If a relocation or design modification of detention facilities is necessary or desirable, the Parties will make a good faith effort to cooperate in making such amendments to the Post Construction Storm Water Management Plan Maintenance Agreement and Easement as are needed to accommodate such relocation or design modification, which modification and amendments shall be in form and content satisfactory to the City Engineer.

B. Annexation. Subdivider hereby agrees not to directly or indirectly fund or pursue, or encourage any other person to fund or pursue, any lawsuit or other action contesting annexation of the Subdivision, or any part thereof, by the City. Subdivider agrees that the City shall not be obligated to annex the Subdivision.

C. All public improvements within the Plat shall be constructed to City approved specifications. The City shall have access to, over and otherwise with respect to all private roadways and private driveways and other improvements for public safety or the exercise of other governmental purposes, including, but not limited to, police, fire and rescue, and for the exercise of the rights granted or reserved to City under this Agreement.

D. Subdivider on a permanent and continuous basis shall provide for proper and continuous maintenance and upkeep within the Subdivision in accordance with ordinances, codes, rules and regulations from time to time adopted or amended by the City and setting forth requirements applicable to maintenance and upkeep of residential real property and related improvements, including, but not limited to, requirements applicable to multifamily housing, residential rental properties and landscaping. When replacement of landscaping is required, the replacement shall be of the same or better quality, maturity, type and quantity as the plants or materials originally required.

E. If Subdivider fails to timely and fully perform any responsibility set forth in Subsection D of this Section within thirty (30) days after written notice from the City of such failure or such later time period as set forth in the next sentence, the City, at its option, may itself take such curative or remedial action as it determines appropriate, or cause such action to be taken, and assess any cost thereof against the Subdivider or against Lot 1 Echo Hills Replat 4 and Lot 1 Echo Hills Replat 5 of the Subdivision as a lien. If it is not possible for Subdivider to perform such responsibility within such thirty (30) day period, such period of time shall be extended by the number of days reasonably necessary to perform such responsibility, provided that Subdivider commences curative actions within the time required by this subsection E and diligently pursues and completes the same as soon as reasonably possible, and provided further that allowing additional time does not present or increase risk of harm to persons or property.

F. Subdivider, before any voluntary or involuntary sale, transfer or conveyance resulting in separate ownership of any two or more parts of the Property, shall record with the Sarpy County Register of Deeds a declaration of covenants running with all property within the Subdivision (except any vacant property sold, transferred or conveyed that will not be served by any public services or public or private improvements to, from, over, under, through or across the remaining property, and that will not serve the remaining property by any public services or public or private improvements to, from, over, under, through or across the vacant

property) and in form and content satisfactory to the City Engineer, which document shall provide for access, use, maintenance, upkeep, replacement and repair of services, equipment, facilities or improvements serving or shared by more than one subdivided portion of the Property, including without limitation, services, equipment, facilities or improvements relating to sewers, gas, water, electric, telecommunications, cable or other utilities, roads, parking or recreation.

- G. Subdivider shall be responsible for ensuring compliance with requirements regarding erosion control when developing the Subdivision.
- H. Any City approval or any notice required under this Agreement must be in writing to be effective.
- I. If any provision of this Agreement is determined unenforceable, the unenforceable provision shall be deemed stricken and the remainder of the Agreement shall be enforced. This Agreement shall be governed and construed in accordance with Nebraska law and the Parties submit to the jurisdiction and venue of the District Court of Sarpy County to resolve any dispute hereunder, and agree not to challenge said jurisdiction or venue
- J. City Engineer Review. All preliminary plans described in this Agreement shall be finalized and subject to review and final approval of the City Engineer prior to building permit approval, grading permit approval, storm water management permit approval, and authorization to construct public improvements as applicable.
- K. Covenants Running With the Land. The final plat and this Agreement and the obligations, understandings and agreements contained or incorporated herein constitute perpetual covenants running with the land, shall be recorded with the Register of Deeds of Sarpy County, Nebraska, and shall be binding, jointly and severally, upon the Subdivider, Developer and Association, and all of their respective successors, assigns, lenders, mortgagees or others gaining or claiming any interest or lien in, to or against any property within the Replatted Area. The covenants herein shall be cumulative to, and not in lieu of, prior covenants running with the land, except to the extent this Agreement requires additional, greater or a higher standard of performance by Subdivider, Developer or Association. City shall have the right, but not the obligation, to enforce any and all covenants. It is further agreed that after City releases the final plat and this Agreement for recording, Subdivider promptly will record the same, along with any other documents or instruments required to be recorded, with the Register of Deeds of Sarpy County, Nebraska. It is expressly agreed, however, that City shall not release the final plat or this Agreement for recording until City is satisfied that Subdivider and Developer have concluded (closed), or made arrangements satisfactory to the City to conclude (close), their respective transactions requiring the actual construction of Private Improvements within the Replatted Area. It is further expressly agreed that, if the condition described in the immediately preceding sentence has not occurred within twelve (12) months after the date of this Subdivision Agreement, neither Subdivider nor Developer shall be entitled without the written consent of the City and any amendments of this Agreement or the Replat as the City Engineer determines necessary, to move forward with the project. Provided, however, the City Administrator periodically may extend the time for performance under this Section 16.

14. Staking Bond. Developer shall provide the City a staking bond satisfactory to City Engineer prior to City's release of the final plat of the Replatted Area.

15. Public Access Roads or Driveways. Direct vehicular access to abutting streets shall be limited as indicated on the Replat, as finally approved by the City in the final plat. Roads and driveways identified in Exhibit "A" for use of the public shall be constructed to City approved specifications and shall not be less than seven inches (7") P.C. concrete paving. The City shall have access to and over such roadways and driveways for any purpose it deems appropriate in the exercise of its general governmental powers, including but not limited to, inspection, police, fire and rescue and other public safety purposes, and the exercise of all rights granted to City by the terms of the Subdivision Agreement.

16. Easements. All proposed easements by the Subdivider, and easements required by the City, as set forth in Exhibit "A," for existing, proposed, or relocated public or private or shared improvements (sewers, utilities, roads or other infrastructure) shall be granted by instruments separate from the final plat, in form and content satisfactory to the City Engineer ("Easements"). Release of the final plat for recording shall be conditioned on execution and delivery of Easements for recording. The Easement documents shall outline rights, obligations and terms of the easements. Easements shall be recorded at the time of recording the final plat and copies of recorded Easements shall be provided to the City. Any proposed modification of any Easements shall be subject to approval of, and in form and content satisfactory to, the City Engineer, and recording of the modification by the Subdivider immediately after said appeal is provided.

17. Right to Enforce. Provisions of this Agreement may be enforced at law or in equity by the owners of land within the Replatted Area and may be enforced by the City at law, in equity or such other remedy as City determines appropriate. All rights and remedies of a party, whether specified in this Agreement or otherwise provided, are cumulative.

18. Ownership Representation. Kevin James for Echo Hills Apartments LLC, by signing below and the Final Plat of Echo Hills Lot 1 Replat 5, and Kevin James for Echo Hills Almc LLC, by signing below, does warrant and represent that it has executed the Final Plat by and through an authorized person, and that it is and shall continue to be the sole owner of 100% of the Replatted Area at date of execution of this Agreement and at date of recording the final plat.

19. Public Access Roads or Driveways. Direct vehicular access to abutting streets shall be limited as indicated on the Replat, as finally approved by the City in the final plat. Roads and driveways identified in Exhibit "D" for use of the public shall be constructed to City approved specifications and shall not be less than seven inches (7") P.C. concrete paving. The City shall have access to and over such roadways and driveways for any purpose it deems appropriate in the exercise of its general governmental powers, including but not limited to, inspection, police, fire and rescue and other public safety purposes, and the exercise of all rights granted to City by the terms of the Subdivision Agreement.

20. Entire Agreement. This Agreement represents the entire agreement and understanding, and supersedes all prior understandings and agreements, written or oral, of the parties with respect to the matters contained herein. The Agreement only may be amended by a written amendment executed by all parties.

21. Severability. If any part of this Agreement is held by a court of competent jurisdiction to be illegal or unenforceable, the illegality or unenforceability shall not affect the remainder of this Agreement, and this Agreement shall be construed as if such illegal or unenforceable provision had never been included herein.

**22. Recitals/Exhibits Summary.** The recitals set forth on pages 1 and 2 above are incorporated herein by reference and made a part of this Agreement. Except as otherwise noted, the following attached Exhibits were prepared by TD2 Engineering & Surveying engineers for Subdivider. The Exhibits (Exhibits "A" thru "J") are attached hereto and made a part of this Agreement, and said Exhibits are incorporated herein by this reference as follows, together with any other documents or instruments referenced in this Agreement:

Exhibit "A"	Final Plat
Exhibit "B"	Conditional Use Permits
Exhibit "C"	Paving Plan
Exhibit "D"	Planned Unit Development ("PUD") Site Plan
Exhibit "E"	Landscaping Plan
Exhibit "F"	Drainage Study (Executive Summary)
Exhibit "G"	Post Construction Storm Water Management Plan
Exhibit "H"	Utility Plan
Exhibit "I"	Sewer Connection Agreement
Exhibit "J"	Post Construction Storm Water Management Plan Maintenance Agreement and Easement

IN WITNESS WHEREOF, we, the Parties hereto, by our respective duly authorized agents, hereto affix our signatures the day and year first above written.

Owner:

Echo Hills Apartments LLC, a Nebraska limited liability company

By:

\_\_\_\_\_

Date: \_\_\_\_\_

Owner:

Echo Hills Almc LLC, a Nebraska limited liability company

By:

\_\_\_\_\_

Date: \_\_\_\_\_

ACKNOWLEDGMENT OF NOTARY

STATE OF NEBRASKA )  
 )  
COUNTY OF \_\_\_\_\_ )

On this \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_, before me a Notary Public, duly commissioned and qualified in and for said County, appeared \_\_\_\_\_ personally known by me to be Owner of Echo Hills Apartments, L.L.C. and Echo Hills Almc L.L.C., a Nebraska limited liability company, and the identical person whose name is affixed to the foregoing Agreement, and acknowledged the execution thereof to be his voluntary act and deed and the voluntary act and deed of said company.

WITNESS my hand and Notarial Seal the day and year last above written.

---

## Notary Public

ATTEST:

## CITY OF LA VISTA

---

Pamela Buethe, City Clerk

Douglas Kindig, Mayor

## ACKNOWLEDGMENT OF NOTARY

STATE OF NEBRASKA )  
 ) ss.  
COUNTY OF SARPY )

On this \_\_\_\_\_ day of \_\_\_\_\_ 20\_\_\_\_, before me a Notary Public, duly commissioned and qualified in and for said County, appeared Douglas Kindig, personally known by me to be the Mayor of the City of La Vista and Pamela Buethe, to me personally known to be the City Clerk of the City of La Vista, the identical persons whose names are affixed to the foregoing Agreement, and they acknowledged the execution thereof to be their voluntary act and deed.

WITNESS my hand and Notarial Seal the day and year last above written.

---

## Notary Public



CITY OF LAVISTA  
CONDITIONAL USE PERMIT

**Conditional Use Permit for an Assisted Living Facility  
(Echo Hills Assisted Living & Memory Care)  
Lot 1 Echo Hills Replat Four**

This Conditional Use Permit issued this 21 day of APRIL, 2020, by the City of La Vista, a municipal corporation in the County of Sarpy County, Nebraska ("City") to, Echo Hills ALMC, LLC, a limited liability company authorized to do business in Nebraska ("Owner"), pursuant to the La Vista Zoning Ordinance.

WHEREAS, Owner wishes to construct and operate an assisted living and memory care facility to be known as Echo Hills Assisted Living and Memory Care upon the following described tract of land within the City of La Vista zoning jurisdiction:

Lot 1 Echo Hills Replat Four, a subdivision in Sarpy County, Nebraska (the "Property") as depicted in Exhibit "A" the final plat; and

WHEREAS, Owner has applied for a Conditional Use Permit for the purpose of constructing and operating an assisted living and memory care facility; and

WHEREAS, the Mayor and City Council of the City of La Vista are agreeable to the issuance of a conditional use permit to the owner for such purposes, subject to certain conditions and agreements as hereinafter provided.

NOW, THEREFORE, BE IT KNOWN THAT subject to the conditions hereof, this Conditional Use Permit is issued to the owner to use the area designated on the final plat as Lot 1 on Exhibit "A" hereto for an assisted living and memory care facility, said use hereinafter being referred to as "Permitted Use or Use".

### **Conditions of the Permit**

The conditions to which the granting of this Permit is subject are as follows:

1. Development and operation on the Property is governed by this Permit. The rights granted by this Permit are transferable and any material breach hereof shall cause Permit to expire and terminate, subject to the rights of the Owner to cure such default or deficiency as set forth in this Permit.
2. In respect to the proposed Uses:
  - a. The site plan (the "Site Plan") showing the Property's boundaries, all existing and proposed easements, proposed structures, parking, access points, and drives, is attached hereto and incorporated herein as Exhibit "B".
  - b. Operations on the property will be limited to and carried out in accordance with the Operational Statement attached as Exhibit "C" and incorporated into this permit by reference.
  - c. Architectural review of the building design, landscaping, and lighting has been completed and the foregoing plans are approved as shown in Exhibits "D" through "F".
  - d. The Property shall be developed and maintained in accordance with the Site Plan and all other Exhibits of this Agreement, as well as the final plat of Lots 1-4 Echo Hills Replat Four ("Final Plat"), Planned Unit Development Plan ("PUD") and Subdivision Agreement applicable to the Property, ("Subdivision Agreement"), as approved by the City and incorporated herein by this reference.

Any modifications to the Site Plan must be submitted to the Chief Building Official for approval. Modification of any other document or Exhibit shall be subject to approval of the City, as directed by the City Administrator, unless otherwise expressly provided in the document or Exhibit to be modified.

- e. All signage, including without limitation design, location, placement and dimensions, shall be subject to approval of the Community Development Department, per the La Vista Zoning Ordinance.
- f. As-built topographic surveys of the storm water detention areas constructed in accordance with the Subdivision Agreement shall be provided to the City before certificates of occupancy are issued for any completed building on the Property, with a requirement that any variances from the approved detention plans be corrected, or certified as inconsequential, to the satisfaction of the City Engineer prior to issuing such certificates.
- g. Owner shall obtain all required permits for the Uses from the City of La Vista.
- h. Owner shall comply (and shall ensure that all structures, appurtenances and improvements on the Property at any time comply) with any applicable federal, state and/or local laws, rules or regulations, as amended or in effect from time to time, including, but not limited to, applicable building codes, fire codes, ADA requirements, and environmental or safety laws, rules or regulations.
- i. Owner hereby indemnifies the City against, and holds the City harmless from, any liability, loss, claim or expense whatsoever (including, but not limited to, reasonable attorney fees and court cost) arising out of or resulting from the acts, omissions or negligence of the Owner or its agents, employees, assigns, suppliers or invitees relating to the Owner's Uses of the Property, including, but not limited to, any liability, loss, claim or expense arising out of or resulting from any violations of any applicable environmental or safety law, rule or regulation but excluding any liability, loss, claim or expense proximately caused by the sole negligence of the City.
- j. A drainage study for the Property has been completed, as referenced in the Subdivision Agreement, with respect to the proposed Uses on Lots 1-4 Echo Hills Replat Four. Owner agrees to comply with requirements related to drainage that are specified in said Subdivision Agreement.
- m. Owner shall ensure that the public-facing front office on the property will be staffed during normal business hours.
- n. If at any time any part of Lot 1 Echo Hills Replat Four is owned by any person or entity other than Owner, all owners shall cooperate and coordinate to carry out Subdivider (as "Subdivider" is defined in the Subdivision Agreement) obligations under the Subdivision Agreement.
- o. There shall not be any outside storage of materials. All trash receptacles, benches and planters shall be placed on property and securely fastened to building or concrete. Trash dumpsters shall be placed with a trash enclosure of six feet in height and screened accordingly.
- p. Landscaping requirements from Section 7.17 of the City of La Vista Zoning Ordinance shall be satisfied and maintained in accordance with the approved landscaping plan (Exhibit "D") and the requirements of the Gateway Corridor District.
- q. This continuing care facility is intended for assisted living and memory care. Facilities shall be exclusively operated for, marketed and leased to, and occupied by persons age 55 and older, or as otherwise required to provide reasonable accommodations to disabled residents under applicable laws, rules or regulations. To carry out this requirement, Owner shall:
  - (i) From time to time during this permit, adopt, publish and adhere to written rules, policies and procedures to implement and carry out said requirement in accordance with 24 CFR Section 100.306, as adopted, amended or superseded from time to time, subject to review and approval of the City Administrator, which approval shall not be withheld or refused so long as the rules, policies and procedures satisfy the requirements of "c" above and 24 CFR Section 100.306; and
  - (ii) Take all other actions during this permit as may be required from time to time under the Federal Fair Housing Act, Housing for Older Persons Act of 1995, Nebraska Fair Housing Act, or any other applicable laws, rules or regulations, as adopted, amended or superseded

from time to time, to carry out this subparagraph "c" in accordance with all applicable requirements, and specifically to qualify and continue the qualification of the facility as senior housing exempt from any applicable familial status protections.

3. The Owner's right to maintain the Uses of the Property, as contemplated by this Permit, shall be based on the following conditions:
  - a. An annual inspection to determine compliance with the conditions of this Permit. The Permit may be revoked (with respect to a particular Use) only upon a finding by the City that there is a material violation of the material terms of this Permit if the violation occurs after written notice from the City to Owner and opportunity to cure in the time and manner described below.
  - b. Construction will be in accordance with the City Building Code. Time limitation for building permits shall be in accordance with the City Building Code. Extensions shall be requested in writing and justifiable cause demonstrated.
  - c. All obsolete or unused structures, accessory facilities or materials with an environmental or safety hazard shall be abated and/or removed from the Property at Owner's expense within twelve (12) months of cessation of the Use of the Property as related to said structures, facilities or materials.
4. Notwithstanding any other provision herein to the contrary, this Permit, and all rights granted hereby, shall expire and terminate as to a Permitted Use hereunder upon the first of the following to occur:
  - a. Owner's abandonment of the Permitted Use. There shall be a presumption that the project on the Property has been abandoned if the Owner fails to commence construction of the buildings within the time provided by Section 4(b) above.
  - b. Cancellation, revocation, denial or failure to maintain any federal, state or local permit required for the Uses, and such cancellation, revocation denial or failure to maintain any federal, state or local permit required for the use is not cured in the time and manner described below, so long as curative rights are provided under laws, rules and regulations governing said permit.
  - c. Owner's construction or placement of a storage tank, structure or other improvement on the Property, (except during construction of any phase of the project) not specified in this Permit and Owner's failure to cure such breach in the time and manner described below after City's giving notice thereof.
  - d. Owner's breach of other terms hereof and its failure to cure such breach in the time and manner set forth below.
5. If construction of the improvements on the Property has not been commenced within twelve (12) months from the date of this Permit, this Permit shall be null and void and all rights hereunder shall lapse; provided, however, Owner shall have the right to file for an extension of time pursuant to the La Vista Zoning Ordinance.
6. If the Owner upon the expiration or termination of this Permit fails to promptly remove any remaining safety, environmental or other hazard or nuisance, the City may at its option (but without any obligation to the Owner or any third party to exercise said option) cause the same to be removed at Owner's cost (including, but not limited to, the cost of any excavation and earthwork that is necessary or advisable in connection with the removal thereof) and the Owner shall reimburse the City the costs incurred to remove the same. Owner hereby irrevocably grants the City, its agents and employees the right, provided notice is furnished to the Owner along with a reasonable time to remove or cure such hazard, to enter the Property and to take whatever action as is necessary or appropriate to remove any such hazards or nuisances in accordance with the terms of this Permit, and the right of the City to enter the Property as may be necessary or appropriate to carry out any other provision of this Permit.
7. If any provision, or any portion thereof, contained in this Permit is held to be unconstitutional, invalid, or unenforceable, the remaining provisions hereof, or portions thereof, shall be deemed severable, shall

not be affected, and shall remain in full force and effect.

8. The conditions and terms of this Permit shall constitute covenants running with the land and shall be binding upon, and shall inure to the benefit of, the Owner, its successors and assigns.
9. Delay of City to terminate this Permit on account of breach of Owner of any terms hereof in accordance with the terms hereof shall not constitute a waiver of City's right to terminate this Permit, unless the City has expressly waived said breach. A waiver of the right to terminate upon any breach shall not constitute a waiver of the right to terminate upon a subsequent breach of the terms hereof, whether said breach be of the same or different nature.
10. Cure Rights. Notwithstanding any other provision of this Permit to the contrary, Owner shall be entitled to written notice and opportunity to cure a breach of this Permit as follows. City will notify the Owner in writing of any breach of this Permit and Owner shall be permitted to cure any breach. Such written notice shall specify the particular conditions giving rise to the breach, and, to the extent known, what actions are required to cure such breach. Cure shall be commenced and completed as soon as possible and in all cases within thirty (30) days after City provides notice of breach; provided, however, in any case that cure cannot be completed within 30 days, additional time will be allowed, so long as cure is commenced within the time required in this Section 10 and diligently pursued and completed as soon as is reasonably possible, and allowing additional time does not substantially increase risk of harm to persons or property. City shall have the right to terminate this Permit if a breach is not timely cured.
11. Nothing herein shall be construed to be a waiver or suspension of, or an agreement on the part of the City to waive or suspend, any zoning law or regulation applicable to the premises except to the extent and for the duration specifically authorized by this Permit.
12. Any notice to be given by City hereunder shall be in writing and shall be sufficiently given if sent by regular mail, postage prepaid, addressed as follows:

To Owner:      Echo Hills ALMC, LLC  
                            PO Box 22151  
                            Lincoln, NE 68542

13. All recitals at the beginning of this document and exhibits or other documents referenced in this Permit shall be incorporated herein by reference.
14. Exhibits.      The following exhibits are incorporated herein by reference:

Exhibit "A":	Final Plat
Exhibit "B":	Site Plan
Exhibit "C":	Operating Statement
Exhibit "D":	Landscaping Plan
Exhibit "E":	Site Lighting Plan
Exhibit "F":	Elevation Renderings

**Effective Date:**

This Permit shall take effect upon the filing hereof with the City Clerk a signed original hereof

## THE CITY OF LA VISTA

By Douglas Kindig, Mayor

Douglas Kindig, Mayor

Attest:

Pamela A. Buethe  
Pamela A Buethe, CMC

Pamela A Buethe, CMC  
City Clerk




#### ACKNOWLEDGMENT OF NOTARY

STATE OF NEBRASKA )  
 ) ss.  
COUNTY OF SARPY )

On this 8th day of July, 2020, before me a Notary Public, duly commissioned and qualified in and for said County, appeared Douglas Kindig, personally known by me to be the Mayor of the City of La Vista and Pamela Buethe, to me personally known to be the City Clerk of the City of La Vista, the identical persons whose names are affixed to the foregoing Permit, and they acknowledged the execution thereof to be their voluntary act and deed.

WITNESS my hand and Notarial Seal the day and year last above written.



Rita M. Ramirez

**CONSENT AND AGREEMENT** The undersigned does hereby consent and agree to the conditions of this permit and that the terms hereof constitute an agreement on the part of the undersigned to fully and timely perform each and every condition and term hereof, and the undersigned does hereby warrant, covenant and agree to fully and timely perform and discharge all obligations and liabilities herein required by Owner to be performed or discharged.

Owner:

Echo Hills ALMC, LLC  
a limited liability company

By: Rey J. S., it's owner


## ACKNOWLEDGMENT OF NOTARY

STATE OF NEBRASKA )  
COUNTY OF Douglas )



On this 15<sup>th</sup> day of June, 2020, before me a Notary Public, duly commissioned and qualified in and for said County, appeared KEVIN JAMES personally known by me to be an owner of Echo Hills ALMC, L.L.C., a limited liability company, and the identical person whose name is affixed to the foregoing Permit, and acknowledged the execution thereof to be his voluntary act and deed and the voluntary act and deed of said company.

WITNESS my hand and Notarial Seal the day and year last above written.

Reverend Trautman  
Notary Public







VICINITY MAP

SITE KEY NOTES

- A. TRAIL ENCLOSURE LOCATION
- B. MONUMENT SIGN LOCATION
- C. DRIVE THRU SIGN LOCATION
- D. PROPOSED ADA STALLS
- E. PROPOSED ACCESS LOCATION
- F. PROPOSED FENCE LOCATION
- G. PROPOSED SPEED BUMP
- H. PROPOSED SPEED HILL & PEDESTRIAN CROSSING

LEGAL DESCRIPTION

ECHO HILLS PLAT 4, LOTS 1-4, BEING A REPLAT OF LOTS 1 & 4, ECHO HILLS A SUBDIVISION IN SHAY COUNTY, NEBRASKA.

LEGEND

- PROPOSED P.C.C. PAVEMENT
- PROPOSED P.C.C. SIDEWALK
- PROPOSED SIDEWALK SWINGER
- PARCEL BOUNDARY
- PROPOSED LOT LINES
- BUILDING SCALE
- LANDSCAPE NETWORK
- PROPOSED ACCESS EASEMENT
- PROPOSED STREAM CHANNEL
- PERIMETER SURVEY LINE/SHADE AS SHOWN ON THE FINAL PLAT OF ECHO HILLS.
- UTILITY EASEMENT GRANTED BY OWNER
- PUBLIC POWER DISTRICT AND TELEPHONE CONTRACTOR IN THE FINAL PLAT OF ECHO HILLS.
- EASEMENT AND RIGHT-OF-WAY GRANTED BY OWNER TO THE PUBLIC POWER DISTRICT OF OMAHA RECORDED AS EASEMENT 1000 IN THE PLAT BOOKS OF SHAY COUNTY RECORDS.

BUILDING HEIGHT

LOT NUMBER	BUILDING NUMBER/NAME	STOREYS	HEIGHT
1	ASSISTED LIVING	2	35'
	MEMORY CARE	1	20'-0"
2	BUILDING 1	3	4F MAX
	BUILDING 2	3	4F MAX
	BUILDING 3	3	4F MAX
	BUILDING 4	3	4F MAX
3	RETAIL	1	20'-0"
4	RETAIL	1	20'-0"

SITE STATISTICS

LOT NUMBER	PROPOSED ZONING	LOT SIZE (SF/AC)	BUILDING COVERAGE (SF)	BUILDING COVERAGE (%)	GROSS FLOOR (SF)	PAVEMENT AREA (SF)	TOTAL IMPERVIOUS (SF)	TOTAL IMPERVIOUS (%)	OPEN SPACE (SF)	TOTAL OPEN SPACE (%)
LOT 1	R-3 (PUD)	185,737 SF / 2.806 AC	8,116	37	125,431 SF	34,589	98,714	66 %	45,544	44 %
LOT 2	R-3 (PUD)	251,191 SF / 3.672 AC	9,588	32	237,260 SF	55,857	177,187	78 %	73,127	36 %
LOT 3	G-1 (PUD)	77,337 SF / 1.171 AC	8,400	12	8,400 SF	44,160	8,700	72 %	30,324	27 %
LOT 4	C-1 (PUD)	45,000 SF / 1.107 AC	5,345	11	5,345 SF	18,170	34,410	61 %	23,775	44 %

PARKING SUMMARY

LOT NUMBER	PARAMETERS	REQUIRED STALLS	PROVIDED STALLS
1	60 ASSISTED LIVING UNITS / 20 MEMORY CARE UNITS	80 + 24 EMPLOYEES**	92
2	210 UNITS	185 COVERED	137
3	280 UNITS/OUTDOOR SEATING	281	309
4	154 UNITS / OUTDOOR SEATING	154 + EMPLOYEE	124
	4,200 SF	21	23

\*\*ASSISTED LIVING RESIDENTS OPERATE VEHICLES & MEMORY CARE RESIDENTS DO NOT OPERATE VEHICLES

PHASING INFORMATION

PHASE NUMBER	LOT NUMBER	PROPOSED USE
PHASE 1	LOT 1	ASSISTED LIVING
PHASE 2	LOT 2	MULTIFAMILY
PHASE 3	LOT 3	COMMERCIAL
PHASE 4	LOT 4	COMMERCIAL



thompson, dreesen & dorner, inc.  
10836 Old Mill Rd  
Omaha, NE 68154  
p.402.330.8860 [www.td2co.com](http://www.td2co.com)

Project Number

Echo Hills Plat 4  
Lots 1 - 4

**Exhibit B**

Client Name  
West Management  
L.L.C.



Professional Seal

No.	Description	MM/DD/YY
1	Updates Per City Comments	07/25/20
2	Updates to Relief Construction Design	07/25/20
3	Updates to Zoning Count	07/25/20
4	...	...
5	...	...
6	...	...
7	...	...
8	...	...
9	...	...
10	...	...
11	...	...
12	...	...
13	...	...
14	...	...
15	...	...
16	...	...
17	...	...
18	...	...
19	...	...
20	...	...
21	...	...
22	...	...
23	...	...
24	...	...
25	...	...
26	...	...
27	...	...
28	...	...
29	...	...
30	...	...
31	...	...
32	...	...
33	...	...
34	...	...
35	...	...
36	...	...
37	...	...
38	...	...
39	...	...
40	...	...
41	...	...
42	...	...
43	...	...
44	...	...
45	...	...
46	...	...
47	...	...
48	...	...
49	...	...
50	...	...
51	...	...
52	...	...
53	...	...
54	...	...
55	...	...
56	...	...
57	...	...
58	...	...
59	...	...
60	...	...
61	...	...
62	...	...
63	...	...
64	...	...
65	...	...
66	...	...
67	...	...
68	...	...
69	...	...
70	...	...
71	...	...
72	...	...
73	...	...
74	...	...
75	...	...
76	...	...
77	...	...
78	...	...
79	...	...
80	...	...
81	...	...
82	...	...
83	...	...
84	...	...
85	...	...
86	...	...
87	...	...
88	...	...
89	...	...
90	...	...
91	...	...
92	...	...
93	...	...
94	...	...
95	...	...
96	...	...
97	...	...
98	...	...
99	...	...
100	...	...
101	...	...
102	...	...
103	...	...
104	...	...
105	...	...
106	...	...
107	...	...
108	...	...
109	...	...
110	...	...
111	...	...
112	...	...
113	...	...
114	...	...
115	...	...
116	...	...
117	...	...
118	...	...
119	...	...
120	...	...
121	...	...
122	...	...
123	...	...
124	...	...
125	...	...
126	...	...
127	...	...
128	...	...
129	...	...
130	...	...
131	...	...
132	...	...
133	...	...
134	...	...
135	...	...
136	...	...
137	...	...
138	...	...
139	...	...
140	...	...
141	...	...
142	...	...
143	...	...
144	...	...
145	...	...
146	...	...
147	...	...
148	...	...
149	...	...
150	...	...
151	...	...
152	...	...
153	...	...
154	...	...
155	...	...
156	...	...
157	...	...
158	...	...
159	...	...
160	...	...
161	...	...
162	...	...
163	...	...
164	...	...
165	...	...
166	...	...
167	...	...
168	...	...
169	...	...
170	...	...
171	...	...
172	...	...
173	...	...
174	...	...
175	...	...
176	...	...
177	...	...
178	...	...
179	...	...
180	...	...
181	...	...
182	...	...
183	...	...
184	...	...
185	...	...
186	...	...
187	...	...
188	...	...
189	...	...
190	...	...
191	...	...
192	...	...
193	...	...
194	...	...
195	...	...
196	...	...
197	...	...
198	...	...
199	...	...
200	...	...
201	...	...
202	...	...
203	...	...
204	...	...
205	...	...
206	...	...
207	...	...
208	...	...
209	...	...
210	...	...
211	...	...
212	...	...
213	...	...
214	...	...
215	...	...
216	...	...
217	...	...
218	...	...
219	...	...
220	...	...
221	...	...
222	...	...
223	...	...
224	...	...
225	...	...
226	...	...
227	...	...
228	...	...
229	...	...
230	...	...
231	...	...
232	...	...
233	...	...
234	...	...
235	...	...
236	...	...
237	...	...
238	...	...
239	...	...
240	...	...
241	...	...
242	...	...
243	...	...
244	...	...
245	...	...
246	...	...
247	...	...
248	...	...
249	...	...
250	...	...
251	...	...
252	...	...
253	...	...
254	...	...
255	...	...
256	...	...
257	...	...
258	...	...
259	...	...
260	...	...
261	...	...
262	...	...
263	...	...
264	...	...
265	...	...
266	...	...
267	...	...
268	...	...
269	...	...
270	...	...
271	...	...
272	...	...
273	...	...
274	...	...
275	...	...
276	...	...
277	...	...
278	...	...
279	...	...
280	...	...
281	...	...
282	...	...
283	...	...
284	...	...
285	...	...
286	...	...
287	...	...
288	...	...
289	...	...
290	...	...
291	...	...
292	...	...
293	...	...
294	...	...
295	...	...
296	...	...
297	...	...
298	...	...
299	...	...
300	...	...
301	...	...
302	...	...
303	...	...
304	...	...
305	...	...
306	...	...
307	...	...
308	...	...
309	...	...
310	...	...
311	...	...
312	...	...
313	...	...
314	...	...
315	...	...
316	...	...
317	...	...
318	...	...
319	...	...
320	...	...
321	...	...
322	...	...
323	...	...
324	...	...
325	...	...
326	...	...
327	...	...
328	...	...
329	...	...
330	...	...
331	...	...
332	...	...
333	...	...

## Operating Statement

### **Echo Hills Assisted Living and Memory Care**

The Echo Hills Assisted Living and Memory Care project will include an 80 unit assisted living and memory care facility consisting of a two-story, 60 unit assisted living building with a one-story wing that will include 20 memory care units. All the units will be rented at market rates and will include 24-hour nursing care for residents that will be tailored to their specific needs. A private courtyard, library, exercise room, daily dining, and shuttle service will be provided for the assisted living residents, while the memory care facility will include a private yard for its residents and controlled access. A total of 10 to 15 full time and part time administrative, nursing, nutrition, and property management positions will be required to operate the facility at any one time. A total of approximately 40 staff will be employed. The property will be managed by MJ Senior Housing, which currently manages several similar facilities in Omaha, Lincoln, and across eastern Nebraska. The facility will be staffed with an Executive Director who will oversee the operations on a daily basis and facilities staff will be available 24 hours a day for any maintenance concerns. The project will be a class A facility and we expect to be 95% full within 18 months of opening. Construction is targeted to start in fall of 2020 and open up in early 2022.



#### LANDSCAPE REQUIREMENTS

STREET FRONTAGE (SECTION 07.17.03.02) - 144TH STREET  
144TH STREET FRONTAGE 966' -  
TREES REQUIRED (1 TREE / 40 LF FRONTAGE) 966' / 40' = 24 TREES  
TREES PROVIDED = 24 TREES

STREET FRONTAGE (SECTION 07.17.03.02) - ECHO HILLS DRIVE  
ECHO HILLS DRIVE FRONTAGE 865' - ACCESS DRIVES 88' = 687'  
TREES REQUIRED (1 TREE / 40 LF FRONTAGE) 687' / 40' = 17 TREES  
TREES PROVIDED = 17 TREES

STREET FRONTAGE (SECTION 07.17.03.02) - 144TH STREET  
144TH STREET FRONTAGE 815' - ACCESS DRIVES 146' = 647'  
TREES REQUIRED (1 TREE / 40 LF FRONTAGE) 647' / 40' = 16 TREES  
TREES PROVIDED = 16 TREES

STREET FRONTAGE (SECTION 07.17.03.02) - CHANDLER ROAD  
CHANDLER ROAD FRONTAGE 531'  
TREES REQUIRED (1 TREE / 40 LF FRONTAGE) 531' / 40' = 13 TREES  
TREES PROVIDED = 13 TREES

PARKING AREA INTERIOR LANDSCAPING (SECTION 07.17.03.02)  
PARKING STALLS = 35  
INTERIOR LANDSCAPING REQUIRED (10 SF / PARKING STALL) = 350 SF  
INTERIOR LANDSCAPING PROVIDED = 1,132 SF

PARKING AREA EXTERIOR LANDSCAPING (SECTION 07.17.03.02)  
PARKING LOT STREET FRONTAGE = 971'  
TREES REQUIRED (1 TREE / 40 LF STREET FRONTAGE) = 24 TREES  
TREES PROVIDED = 24

PARKING AREA SCREENING (SECTION 07.17.04.01)  
PARKING LOT SCREENING = 936 LF  
MINIMUM 3' HIGH VEGETATIVE SCREENING

## Exhibit D

LAMP  
RYNEARSON  
14710 W. DODGE RD. STE. 100  
OMAHA, NE 68154  
402.331.5444  
LampRynearson.com

PRELIMINARY

NOT RELEASED FOR CONSTRUCTION  
ZACHARY R. FERGUSON  
LA-301

PLANNED UNIT DEVELOPMENT  
OVERALL LANDSCAPE PLAN

ECHO HILLS ASSISTED LIVING AND MEMORY CARE  
LA VISTA, NEBRASKA



Know what's below.  
Call before you dig.

PENNSYLVANIA

DESIGNER / DRAFTER  
ZACHARY R. FERGUSON  
DATE  
MAY 22, 2002  
PROJECT NUMBER  
0120013  
BOOK AND PAGE

SHEET

1

**LANDSCAPE KEYNOTES**

- 1. 6' HEIGHT WHITE VINYL FENCE
- 2. 4' HEIGHT WHITE VINYL FENCE
- 3. 6' WIDTH BENCH
- 4. 48" WIDTH TABLE WITH (4) MOBILE CHAIRS
- 5. PROPOSED SIGN
- 6. TRASH ENCLOSURE. REFER TO ARCHITECTURAL PLANS FOR ADDITIONAL INFORMATION.
- 7. ELECTRICAL EQUIPMENT. REFER TO ELECTRICAL PLANS FOR ADDITIONAL INFORMATION.
- 8. RETAINING WALL. REFER TO CIVIL PLANS FOR ADDITIONAL INFORMATION.


**1 LANDSCAPE PLAN**

**PLANT SCHEDULE**

CODE	BOTANICAL NAME	COMMON NAME	PLANTING SIZE	HEIGHT	WIDTH
<b>DECIDUOUS TREES</b>					
AS	ACER MIYABEI 'STATE STREET'	STATE STREET MAPLE	2.5" CAL	40	40
GH	GLECHMA TRACHANTHOS VAR. INERMIS 'VALERIA'	HAWAII HONEYLOCUST	2.5" CAL	40	40
GP	GINKGO BILOBA 'PRINCETON SENTRY'	PRINCETON SENTRY GINKGO	2.5" CAL	40	15
QB	QUERCUS BICOLOR	SNAKE EYE OAK	2.5" CAL	60	60
MS	MALUS 'SNOWDRIFT'	SNOWDRIFT CRABAPPLE	2.5" CAL	15-20	20-25
SR	SYRINGA RETICULATA	JAPANESE TREE LILAC	2.5" CAL	20-25	15-20
<b>CONIFEROUS TREES</b>					
JV	JUNIPERUS VIRGINIANA 'TAYLOR'	TAYLOR JUNIPER	6' HT	25	3
PG	PICEA GLAUCA	BLACK HILLS SPRUCE	6' HT	25	15
PH	PINUS HELDRECHSII	BOSNIAN PINE	6' HT	40	10
<b>SHRUBS AND PERENNIALS</b>					
SB	SPIRAEA BETULIFOLIA 'TOR'	BIRCHLEAF SPIREA	5 GAL	2-3	2-3
SM	SYRINGA MELIIFERA 'PAULS'	DAIRY KOREAN LILAC	5 GAL	4-5	3-4
CS	CORNUS STOLONIFERA 'TARROW'	ARCTIC FIRE DOGWOOD	5 GAL	3-4	3-4
BG	BUXUS 'GREEN VELVET'	GREEN VELVET BOXWOOD	5 GAL	3-4	3-4
JC	JUNIPERUS CHINENSIS 'SEA GREEN'	SEA GREEN JUNIPER	5 GAL	4-6	4-6
JS	JUNIPERUS SABINA 'BUFFALO'	BUFFALO JUNIPER	5 GAL	1	6-8
CA	CALAMAGROSTIS X ACUTIFLORA 'KARL FISCHER'	FEATHER REED GRASS	1 GAL	2-3	2-3
SH	SPOROBOLUS HETEROLEPSIS	PRairie DROPSSEED	1 GAL	2-3	2-3
RA	RHUS AROMATICA 'DRO-LON'	DRO-LON SUMAC	5 GAL	2-3	6-8
RN	ROSA X 'WOLESA'	FLOWER CARPET YELLOW ROSE	5 GAL	2-3	3-4
FC	FORSYTHIA X 'COURTASOL'	GOLD TIE FORSYTHIA	5 GAL	1-2	4
HA	HYDRANGEA ARBORESCENS 'ANNABELLE'	ANNABELLE HYDRANGEA	5 GAL	4-5	4-5
HD	HOSTA 'GUACAMOLE'	GUACAMOLE HOSTA	1 GAL	1.5-2	3-3.5
DS	DICENTRA SPECTABILIS 'NORDWAL'	VALENTINE BLEEDING HEART	1 GAL	2.5-3	3-3.5
<b>SURFACE RESTORATION SCHEDULE</b>					
SHREDDED HARDWOOD MULCH - INSTALL TO MINIMUM 3" DEPTH. SUBMIT SAMPLE TO OWNER'S REPRESENTATIVE PRIOR TO INSTALLATION.					
LAWN 500 - RFT TURF TYPE FESCUE BY GOOD VALLEY FARMS (WWW.GOODVALLEYFARMS.COM) OR APPROVED EQUAL. INSTALL PER SUPPLIER'S SPECIFICATIONS. REMOVE NETTING PRIOR TO INSTALLATION. ALL AREAS RECEIVING RFT TURF TYPE FESCUE SHALL HAVE CONDITIONED SOILS.					
STONE GROUNDCOVER - 2" - 4" RIVER ROCK GROUNDCOVER WITH GEOTEXTILE UNDERLAYMENT. INSTALL TO A MINIMUM 6" DEPTH. SUBMIT SAMPLE TO OWNER'S REPRESENTATIVE PRIOR TO INSTALLATION.					
RUBBER MULCH GROUNDCOVER - INSTALL TO MINIMUM 3" DEPTH. SUBMIT SAMPLE TO OWNER'S REPRESENTATIVE PRIOR TO INSTALLATION.					

**811**  
Call before you dig.  
811

**NOT RELEASED FOR CONSTRUCTION**  
ZACHARY R. FEROLIS  
DATE: MAY 22, 2020  
PROJECT NUMBER: 012013  
BOOK AND PAGE: SHEET  
L1.1





ILLUMINANCE [FC]			
Label	Avg	Max	Min
NE VERT	0.60	0.0	0.0
NW VERT	0.51	0.0	0.0
SW VERT	0.34	9.9	0.0
W VERT	0.00	0.0	0.0

ECHO HILLS  
SITE PHOTOMETRICS  
SCALE: 1" = 40'-0" ON 30x42

## Exhibit E

PLANNING	REVIEW
NOT TO BE USED FOR CONSTRUCTION	REVISION SCHEDULE RE-SENT TO BLDG. DEPT. 04/08/2020 FURNISHINGS INTERIOR EXTERIOR


**WEST DEVELOPMENT**  
ECHO HILLS APARTMENTS AND ASSISTED LIVING


SINCLAIR HILL ARCHITECTS T: 402.471.2321 F: 402.470.5511 100 G St., Lincoln, NE 68508 SMA PROJECT NO. A204 Project Number	Exterior Elevations - Assisted Living
---	---------------------------------------

**A204**

EXTERIOR ELEVATION	RE-SENT TO BLDG. DEPT. 04/08/2020
--------------------	-----------------------------------


**Exhibit F**





#### MATERIALS IN COURTYARD & MECHANICAL AREA

#### SUPPLEMENTAL INFORMATION



TRASH ENCLOSURE  
SUPPLEMENTAL INFORMATION

**CITY OF LAVISTA  
CONDITIONAL USE PERMIT**

**Conditional Use Permit for Multiple Family Dwellings  
(Echo Hills Apartments)  
Lot 1 Echo Hills Replat Five**

This Conditional Use Permit is issued this \_\_\_\_\_ day of \_\_\_\_\_ 2022 by the City of La Vista, a municipal corporation in Sarpy County, Nebraska ("City") to Echo Hills Apartments, LLC, a limited liability company authorized to do business in Nebraska ("Owner"), pursuant to the La Vista Zoning Ordinance.

WHEREAS, Owner was granted a Conditional Use Permit by the City Council of the City of La Vista on April 21, 2020 to construct and operate a multiple family dwelling complex to be known as the Echo Hills Apartments (now known as the Echo Park Apartments) upon Lot 2 Echo Hills Replat Four, a subdivision in Sarpy County, Nebraska; and

WHEREAS, Owner has applied for an amended Conditional Use Permit for the purpose of constructing and operating additional multiple family dwelling units as part of the Echo Park Apartment Complex on Lots 3 and 4 Echo Hills Replat Four, being combined with Lot 2 Echo Hills Replat Four through a replatting process to be Lot 1 Echo Hills Replat Five, a subdivision in Sarpy County, Nebraska (the "Property") as depicted in Exhibit "A" the final plat'; and

WHEREAS, the Mayor and City Council of the City of La Vista are agreeable to the issuance of a Conditional Use Permit to the Owner for such purposes, subject to certain conditions and agreements as hereinafter provided (the "Permit").

NOW, THEREFORE, BE IT KNOWN THAT subject to the conditions hereof, this Permit is issued to the Owner to use the Property for the purposes described above, said use hereinafter being referred to interchangeably as a "Permitted Uses" or "Uses".

**Conditions of the Permit**

The conditions to which the granting of this Permit is subject are as follows:

1. Development and operation on the Property is governed by this Permit. The rights granted by this Permit are transferable and any material breach hereof shall cause Permit to expire and terminate, subject to the rights of the Owner to cure such default or deficiency as set forth in this Permit.
2. In respect to the proposed Uses:
  - a. The site plan (the "Site Plan") showing the Property's boundaries, all existing and proposed easements, proposed structures, parking, access points, and drives, is attached hereto and incorporated herein as Exhibit "B".
  - b. Operations on the property will be limited to and carried out in accordance with the Operational Statement attached as Exhibit "C" and incorporated into this permit by reference.
  - c. Architectural review of the building design, landscaping, and lighting must be completed prior to issuance of building permits, and the foregoing plans are approved as shown in Exhibits "D" through "F".
  - d. The Property shall be developed and maintained in accordance with the Site Plan and all other Exhibits of this Agreement, as well as the final plat of Lots 1-4 Echo Hills Replat Four ("Final Plat"), Planned Unit Development Plan ("PUD") and Subdivision Agreement applicable to the Property,

("Subdivision Agreement"), as approved by the City and incorporated herein by this reference. Any modifications to the Site Plan must be submitted to the Chief Building Official for approval. Modification of any other document or Exhibit shall be subject to approval of the City, as directed by the City Administrator, unless otherwise expressly provided in the document or Exhibit to be modified.

- e. All signage, including without limitation design, location, placement and dimensions, shall be subject to approval of the Community Development Department, per the La Vista Zoning Ordinance.
- f. As-built topographic surveys of the storm water detention areas constructed in accordance with the Subdivision Agreement shall be provided to the City before certificates of occupancy are issued for any completed building on the Property, with a requirement that any variances from the approved detention plans be corrected, or certified as inconsequential, to the satisfaction of the City Engineer prior to issuing such certificates.
- g. No vehicle repair (other than emergency maintenance such as changing a tire), inoperable or abandoned vehicles, or storage of vehicles shall be allowed in the parking areas on the Property shown on Exhibit "B". The Owner shall have seventy-two (72) hours after notice from the City or other appropriate political subdivision to correct any violation or cause the removal of any such vehicle that is in violation.
- h. Owner shall obtain all required permits for the Uses from the City of La Vista.
- i. Owner shall comply (and shall ensure that all structures, appurtenances and improvements on the Property at any time comply) with any applicable federal, state and/or local laws, rules or regulations, as amended or in effect from time to time, including, but not limited to, applicable building codes, fire codes, ADA requirements, and environmental or safety laws, rules or regulations.
- j. Owner hereby indemnifies the City against, and holds the City harmless from, any liability, loss, claim or expense whatsoever (including, but not limited to, reasonable attorney fees and court cost) arising out of or resulting from the acts, omissions or negligence of the Owner or its agents, employees, assigns, suppliers or invitees relating to the Owner's Uses of the Property, including, but not limited to, any liability, loss, claim or expense arising out of or resulting from any violations of any applicable environmental or safety law, rule or regulation but excluding any liability, loss, claim or expense proximately caused by the sole negligence of the City.
- k. A drainage study for the Property has been completed, as referenced in the Subdivision Agreement, with respect to the proposed Uses on Lot 1 Echo Hills Replat Four and Lot 1 Echo Hills Replat Five. Owner agrees to comply with requirements related to drainage that are specified in said Subdivision Agreement.
- m. Owner shall ensure that the leasing and business office on the property will be staffed during normal business hours.
- n. If at any time any part of Lot 1 Echo Hills Replat Five is owned by any person or entity other than Owner, all owners shall cooperate and coordinate to carry out Subdivider (as "Subdivider" is defined in the Subdivision Agreement) obligations under the Subdivision Agreement.
- o. There shall not be any outside storage of materials. All trash receptacles, benches and planters shall be placed on property and securely fastened to building or concrete. Trash dumpsters shall be placed with a trash enclosure of six feet in height and screened accordingly.
- p. Landscaping requirements from Section 7.17 of the City of La Vista Zoning Ordinance shall be satisfied and maintained in accordance with the approved landscaping plan (Exhibit "D") and the requirements of the Gateway Corridor District.
- q. The coffee shop or commercial tenant intended to occupy the 1,800 square foot commercial bay in the southwest corner of apartment building #5 must be approved by the Community Development Department prior to lease execution or occupancy so that the potential for vehicles stacking into the public street from the drive-through can be evaluated.

3. The Owner's right to maintain the Uses of the Property, as contemplated by this Permit, shall be based on the following conditions:

- a. An annual inspection to determine compliance with the conditions of this Permit. The Permit may be revoked (with respect to a particular Use) only upon a finding by the City that there is a material violation of the material terms of this Permit if the violation occurs after written notice from the City to Owner and opportunity to cure in the time and manner described below.
  - b. Construction will be in accordance with the City Building Code. Time limitation for building permits shall be in accordance with the City Building Code. Extensions shall be requested in writing and justifiable cause demonstrated.
  - c. All obsolete or unused structures, accessory facilities or materials with an environmental or safety hazard shall be abated and/or removed from the Property at Owner's expense within twelve (12) months of cessation of the Use of the Property as related to said structures, facilities or materials.
4. Notwithstanding any other provision herein to the contrary, this Permit, and all rights granted hereby, shall expire and terminate as to a Permitted Use hereunder upon the first of the following to occur:
  - a. Owner's abandonment of the Permitted Use. There shall be a presumption that the project on the Property has been abandoned if the Owner fails to commence construction of the buildings within the time provided by Section 4(b) above.
  - b. Cancellation, revocation, denial or failure to maintain any federal, state or local permit required for the Uses, and such cancellation, revocation denial or failure to maintain any federal, state or local permit required for the use is not cured in the time and manner described below, so long as curative rights are provided under laws, rules and regulations governing said permit.
  - c. Owner's construction or placement of a storage tank, structure or other improvement on the Property, (except during construction of any phase of the project) not specified in this Permit and Owner's failure to cure such breach in the time and manner described below after City's giving notice thereof.
  - d. Owner's breach of other terms hereof and its failure to cure such breach in the time and manner set forth below.
5. If construction of the improvements on the Property has not been commenced within twelve (12) months from the date of this Permit, this Permit shall be null and void and all rights hereunder shall lapse; provided, however, Owner shall have the right to file for an extension of time pursuant to the La Vista Zoning Ordinance.
6. If the Owner upon the expiration or termination of this Permit fails to promptly remove any remaining safety, environmental or other hazard or nuisance, the City may at its option (but without any obligation to the Owner or any third party to exercise said option) cause the same to be removed at Owner's cost (including, but not limited to, the cost of any excavation and earthwork that is necessary or advisable in connection with the removal thereof) and the Owner shall reimburse the City the costs incurred to remove the same. Owner hereby irrevocably grants the City, its agents and employees the right, provided notice is furnished to the Owner along with a reasonable time to remove or cure such hazard, to enter the Property and to take whatever action as is necessary or appropriate to remove any such hazards or nuisances in accordance with the terms of this Permit, and the right of the City to enter the Property as may be necessary or appropriate to carry out any other provision of this Permit.
7. If any provision, or any portion thereof, contained in this Permit is held to be unconstitutional, invalid, or unenforceable, the remaining provisions hereof, or portions thereof, shall be deemed severable, shall not be affected, and shall remain in full force and effect.
8. The conditions and terms of this Permit shall constitute covenants running with the land and shall be binding upon, and shall inure to the benefit of, the Owner, its successors and assigns.
9. Delay of City to terminate this Permit on account of breach of Owner of any terms hereof in accordance

with the terms hereof shall not constitute a waiver of City's right to terminate this Permit, unless the City has expressly waived said breach. A waiver of the right to terminate upon any breach shall not constitute a waiver of the right to terminate upon a subsequent breach of the terms hereof, whether said breach be of the same or different nature.

10. Cure Rights. Notwithstanding any other provision of this Permit to the contrary, Owner shall be entitled to written notice and opportunity to cure a breach of this Permit as follows. City will notify the Owner in writing of any breach of this Permit and Owner shall be permitted to cure any breach. Such written notice shall specify the particular conditions giving rise to the breach, and, to the extent known, what actions are required to cure such breach. Cure shall be commenced and completed as soon as possible and in all cases within thirty (30) days after City provides notice of breach; provided, however, in any case that cure cannot be completed within 30 days, additional time will be allowed, so long as cure is commenced within the time required in this Section 10 and diligently pursued and completed as soon as is reasonably possible, and allowing additional time does not substantially increase risk of harm to persons or property. City shall have the right to terminate this Permit if a breach is not timely cured.
11. Nothing herein shall be construed to be a waiver or suspension of, or an agreement on the part of the City to waive or suspend, any zoning law or regulation applicable to the premises except to the extent and for the duration specifically authorized by this Permit.
12. Any notice to be given by City hereunder shall be in writing and shall be sufficiently given if sent by regular mail, postage prepaid, addressed as follows:

To Owner: Echo Hills Apartments, LLC  
PO Box 22151  
Lincoln, NE 68542

13. All recitals at the beginning of this document and exhibits or other documents referenced in this Permit shall be incorporated herein by reference.
14. Exhibits. The following exhibits are incorporated herein by reference:

Exhibit "A":	Final Plat
Exhibit "B":	Site Plan
Exhibit "C":	Operating Statement
Exhibit "D":	Landscaping Plan
Exhibit "E":	Site Lighting Plan
Exhibit "F":	Elevation Renderings

### Effective Date:

This Permit shall take effect upon the filing hereof with the City Clerk a signed original hereof

## THE CITY OF LA VISTA

Attest:

---

Pamela A Buethe, CMC  
City Clerk

## ACKNOWLEDGMENT OF NOTARY

STATE OF NEBRASKA )  
 ) ss.  
COUNTY OF SARPY )

On this \_\_\_\_\_ day of \_\_\_\_\_, 2022, before me a Notary Public, duly commissioned and qualified in and for said County, appeared Douglas Kindig, personally known by me to be the Mayor of the City of La Vista and Pamela Buethe, to me personally known to be the City Clerk of the City of La Vista, the identical persons whose names are affixed to the foregoing Permit, and they acknowledged the execution thereof to be their voluntary act and deed.

WITNESS my hand and Notarial Seal the day and year last above written.

**CONSENT AND AGREEMENT** The undersigned does hereby consent and agree to the conditions of this permit and that the terms hereof constitute an agreement on the part of the undersigned to fully and timely perform each and every condition and term hereof, and the undersigned does hereby warrant, covenant and agree to fully and timely perform and discharge all obligations and liabilities herein required by Owner to be performed or discharged.

Owner:

## Echo Hills Apartments, LLC

By: \_\_\_\_\_, it's owner

## ACKNOWLEDGMENT OF NOTARY

STATE OF NEBRASKA )  
 )  
COUNTY OF \_\_\_\_\_ )

On this \_\_\_\_\_ day of \_\_\_\_\_, 2022, before me a Notary Public, duly commissioned and qualified in and for said County, appeared \_\_\_\_\_ personally known by me to be an owner of Echo Hills Apartments, L.L.C., a limited liability company, and the identical person whose name is affixed to the foregoing Permit, and acknowledged the execution thereof to be his voluntary act and deed and the voluntary act and deed of said company.

WITNESS my hand and Notarial Seal the day and year last above written.

---

## Notary Public



## Exhibit B

Client Name  
**Echo Hills Apartments LLC**

Professional Seal

Revision Dates

No.	Description	MM-DD-YY
1		
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		
21		
22		
23		
24		
25		
26		
27		
28		
29		
30		
31		
32		
33		
34		
35		
36		
37		
38		
39		
40		
41		
42		
43		
44		
45		
46		
47		
48		
49		
50		
51		
52		
53		
54		
55		
56		
57		
58		
59		
60		
61		
62		
63		
64		
65		
66		
67		
68		
69		
70		
71		
72		
73		
74		
75		
76		
77		
78		
79		
80		
81		
82		
83		
84		
85		
86		
87		
88		
89		
90		
91		
92		
93		
94		
95		
96		
97		
98		
99		
100		
101		
102		
103		
104		
105		
106		
107		
108		
109		
110		
111		
112		
113		
114		
115		
116		
117		
118		
119		
120		
121		
122		
123		
124		
125		
126		
127		
128		
129		
130		
131		
132		
133		
134		
135		
136		
137		
138		
139		
140		
141		
142		
143		
144		
145		
146		
147		
148		
149		
150		
151		
152		
153		
154		
155		
156		
157		
158		
159		
160		
161		
162		
163		
164		
165		
166		
167		
168		
169		
170		
171		
172		
173		
174		
175		
176		
177		
178		
179		
180		
181		
182		
183		
184		
185		
186		
187		
188		
189		
190		
191		
192		
193		
194		
195		
196		
197		
198		
199		
200		
201		
202		
203		
204		
205		
206		
207		
208		
209		
210		
211		
212		
213		
214		
215		
216		
217		
218		
219		
220		
221		
222		
223		
224		
225		
226		
227		
228		
229		
230		
231		
232		
233		
234		
235		
236		
237		
238		
239		
240		
241		
242		
243		
244		
245		
246		
247		
248		
249		
250		
251		
252		
253		
254		
255		
256		
257		
258		
259		
260		
261		
262		
263		
264		
265		
266		
267		
268		
269		
270		
271		
272		
273		
274		
275		
276		
277		
278		
279		
280		
281		
282		
283		
284		
285		
286		
287		
288		
289		
290		
291		
292		
293		
294		
295		
296		
297		
298		
299		
300		
301		
302		
303		
304		
305		
306		
307		
308		
309		
310		
311		
312		
313		
314		
315		
316		
317		
318		
319		
320		
321		
322		
323		
324		
325		
326		
327		
328		
329		
330		
331		
332		
333		
334		
335		
336		
337		
338		
339		
340		
341		
342		
343		
344		
345		
346		
347		
348		
349		
350		
351		
352		
353		
354		
355		
356		
357		
358		
359		
360		
361		
362		
363		
364		
365		
366		
367		
368		
369		
370		
371		
372		
373		
374		
375		
376		
377		
378		
379		
380		
381		
382		
383		
384		
385		
386		
387		
388		
389		
390		
391		
392		
393		
394		
395		
396		
397		
398		
399		
400		
401		
402		
403		
404		
405		
406		
407		
408		
409		
410		
411		
412		
413		
414		
415		
416		
417		
418		
419		
420		
421		
422		
423		
424		
425		
426		
427		
428		
429		
430		
431		
432		
433		
434		
435		
436		
437		
438		
439		
440		
441		
442		
443		
444		
445		
446		
447		
448		
449		
450		
451		
452		
453		
454		
455		
456		
457		
458		
459		
460		
461		
462		
463		
464		
465		
466		
467		
468		
469		
470		
471		
472		
473		
474		
475		
476		
477		
478		
479		
480		
481		
482		
483		
484</td		

# EXHIBIT C



P.O. Box 82533 | Lincoln, NE 68501-2533

800-869-03565 | [assurity.com](http://assurity.com)

## Echo Park Apartments Phase 2 Operating Statement


Echo Park Phase 2 will be comprised of one building with 71 units and 16 tuck in garages on the first floor. The Tract of land is comprised of 376,751 sq ft (8.649 Acres). The 71-units will be comprised of a mix of studios, 1 bedroom, and 2-bedroom apartment homes. Additionally, this building will house an approximate 2,000 sq ft coffee shop on the first floor.

Building	Unit Count	Parking Stalls	Garage Stalls
Building 1	30	19	13
Building 2	30	20	13
Building 3	90	67	88
Building 4	60	66	23
Building 5	71	97	16

\*Clubhouse is in Building 3 which includes living room area, pet spa, craft room, study hall, pool area, and grill area

\*Building 5 is anticipating a coffee shop located on first floor of building

# EXHIBIT D



## LANDSCAPE REQUIREMENTS

STREET FRONTAGE (SECTION 07.17.03.02) – 144TH STREET  
144TH STREET FRONTAGE 966' –  
TREES REQUIRED (1 TREE / 40 LF FRONTAGE) 966' / 40' = 24 TREES  
TREES PROVIDED = 26 TREES

STREET FRONTAGE (SECTION 07.17.03.02) – ECHO HILLS DRIVE  
ECHO HILLS DRIVE FRONTAGE 865' – ACCESS DRIVES 88' = 668'  
TREES REQUIRED (1 TREE / 40 LF FRONTAGE) 668' / 40' = 17 TREES  
TREES PROVIDED = 18 TREES

STREET FRONTAGE (SECTION 07.17.03.02) – 146TH STREET  
146TH STREET FRONTAGE 815' – ACCESS DRIVES 168' = 647'  
TREES REQUIRED (1 TREE / 40 LF FRONTAGE) 647' / 40' = 16 TREES  
TREES PROVIDED = 17 TREES

STREET FRONTAGE (SECTION 07.17.03.02) – CHANDLER ROAD  
CHANDLER ROAD FRONTAGE 531'  
TREES REQUIRED (1 TREE / 40 LF FRONTAGE) 531' / 40' = 13 TREES  
TREES PROVIDED = 13 TREES

PARKING AREA, INTERIOR LANDSCAPING (SECTION 07.17.03.06)  
PARKING STALLS = 311  
INTERIOR LANDSCAPING REQUIRED (10 SF / PARKING STALL) = 3,510 SF  
INTERIOR LANDSCAPING PROVIDED = 11,341 SF

PARKING AREA, PERIMETER LANDSCAPING (SECTION 07.17.03.07)  
PARKING LOT STREET FRONTAGE = 615'  
TREES REQUIRED (1 TREE / 40 LF STREET FRONTAGE) = 15 TREES  
TREES PROVIDED = 23

PARKING AREA, SCREENING (SECTION 07.17.04.01)  
MINIMUM 3' HIGH VEGETATIVE SCREENING PROVIDED

## NOTES:

1. SEE SHEET L2.0 FOR PLANT SCHEDULE
2. ALL TURF GRASS AREAS AND LANDSCAPE PLANTINGS SHALL BE IRRIGATED. SEE SHEET L3.0 FOR ADDITIONAL INFORMATION.

**LAMP  
RYNEARSON**  
14710 W. DODGE RD. STE. 100  
OMAHA, NE 68154  
402.466.4608  
LampRynearson.com



PRELIMINARY

NOT RELEASED FOR CONSTRUCTION

ZACHARY R. FERGUS

LA-07

OVERALL LANDSCAPE PLAN

ECHO HILLS APARTMENTS  
LA VISTA, NEBRASKA





ALL UTILITIES ARE SHOWN.  
BASED ON INFORMATION PROVIDED BY THE OWNER.  
THESE UTILITIES ARE SHOWN SO THAT  
THE OWNER CAN LOCATE THEM.  
THE USE OF EXCAVATION EQUIPMENT IS  
NOT RECOMMENDED.  
ALL UTILITIES ARE OWNED  
BY THE OWNER OR BY A CONTRACTOR.


DESIGNER / CHAPTR  
ZACHARY R. FERGUS  
DATE  
JANUARY 3, 2022  
PROJECT NUMBER  
0120015.01-026/027  
BOOK AND PAGE  
BOOK


SHEET


L1.0











#### IRRIGATION NOTES

1. THE CONTRACTOR SHALL MODIFY THE EXISTING IRRIGATION SYSTEM AS NECESSARY, WHILE MAINTAINING FUNCTIONALITY OF THE SYSTEM AT ALL TIMES THROUGHOUT CONSTRUCTION. MODIFICATIONS TO THE EXISTING SYSTEM MAY INCLUDE REMOVAL AND CAP, HORIZONTAL AND/ OR VERTICAL ADJUSTMENT OF SPRINKLER LINES, SPRINKLER HEADS, JUNCTION BOXES, VALVES, PUMPS, BACKFLOW PREVENTER, DRAIN VALVE, MANIFOLD, LATERALS, HEADS, CONTROLLER, AND WIRING. SHALL PROVIDE 100% HEAD TO HEAD COVERAGE TO THE PROPOSED LAWN AND 100% WATERING TO ALL SODED AREAS. CONTRACTOR SHALL COORDINATE WITH THE OWNER PRIOR TO MODIFYING IRRIGATION SYSTEM.
2. THE CONTRACTOR, AT COMPLETION OF CONSTRUCTION OR DURING LANDSCAPING OPERATIONS, SHALL MODIFY THE IRRIGATION SYSTEM AS NECESSARY, WHILE MAINTAINING FUNCTIONALITY OF THE SYSTEM, TO WATER ALL UNDISTURBED AREAS AS NEEDED, COORDINATE WITH THE OWNER PRIOR TO MODIFYING IRRIGATION SYSTEM.
3. IRRIGATION CONTRACTOR TO PROVIDE DESIGN/BUILD IRRIGATION SYSTEM FOR AREAS TO BE IRRIGATED. IRRIGATION SYSTEM DRAWINGS SHALL BE SUBMITTED TO THE ARCHITECT/ENGINEER AND OWNER FOR THEIR RECORDS.
4. ALL SODED AREAS, PLANTING BEDS, AND INTERIOR ISLANDS WITHIN THE LIMITS OF THE PROJECT SHALL BE IRRIGATED. CONTRACTOR SHALL REFER TO LIMITS OF IRRIGATION - THIS SHEET.
5. CONTRACTOR TO COORDINATE LOCATION OF EXISTING VALVES, TIMERS AND HEADS WITH OWNER.

- DRIP IRRIGATION  
(MULCHED PLANTING BEDS)

- SPRAY IRRIGATION  
(TURF GRASS AREAS)

#### IRRIGATION SPECIFICATIONS

1. WITHIN THE LIMITS OF THE PROPOSED LANDSCAPED AREAS SHOWN ON THIS PLAN, CONTRACTOR SHALL PROPOSE A FULLY AUTOMATED IRRIGATION SYSTEM. THE COMPLETED PRESSURIZED SYSTEM INCLUDING WATER SUPPLY, PUMPS, BACKFLOW PREVENTER, DRAIN VALVE, MANIFOLD, VALVES, LATERALS, HEADS, CONTROLLER, AND WIRING, SHALL PROVIDE 100% HEAD TO HEAD COVERAGE TO THE PROPOSED LAWN AND 100% WATERING TO ALL SODED AREAS. CONTRACTOR SHALL COORDINATE WITH THE OWNER PRIOR TO MODIFYING IRRIGATION SYSTEM. AND SHALL TAKE WIND INTO CONSIDERATION WHEN CALCULATING FOR THE POTENTIAL FOR OVERSPRAY. THE UNDISTURBED AREAS SHALL BE WATERED AS NECESSARY. CONTRACTOR SHALL COORDINATE WITH THE OWNER FOR SPRINKLER HEADS, VALVES, PIPING, FITTINGS, CONTROLLERS, WIRING, ETC., OF SIZES AND TYPES ADEQUATE FOR THE AREAS SHOWN. CONTRACTOR SHALL COORDINATE WITH THE OWNER PRIOR TO MODIFYING IRRIGATION SYSTEM. EQUIPMENT SHALL BE INSTALLED PER MANUFACTURER'S RECOMMENDATIONS AND STANDARD INSTALLATION PRACTICES. FINISHED IRRIGATION SYSTEM SHALL COMPLY WITH LOCAL PLUMBING CODE.

2. CONTRACTOR SHALL PREPARE A PROPOSAL EQUIVALENT TO CONSTRUCTION PLANS FOR A FULLY OPERATIONAL IRRIGATION SYSTEM THAT INCLUDES, BUT IS NOT LIMITED TO THE FOLLOWING:

- 2.1. EXISTING AND PROPOSED SITE CONDITIONS
- 2.2. EXISTING AND PROPOSED GALLONAGE
- 2.3. EXISTING IRRIGATION INCLUDING:

  - 2.3.1. CONTROLLER AND WIRING
  - 2.3.2. PUMP AND CONNECTOR WITH SIZE
  - 2.3.3. VALVES INCLUDING MAKE, MODEL, AND SIZE
  - 2.3.4. IRRIGATION MANIFOLDS AND LATERALS WITH SIZES
  - 2.3.5. IRRIGATION HEADS INCLUDING MAKE, MODEL AND SIZE
  - 2.3.6. VALVE BOXES AND EQUIPMENT INCLUDING PRESSURE RELEASE VALVES, SHUT-OFF VALVES AND QUICK COUPLING VALVES
  - 2.3.7. GALLONAGE AND WATERING WINDOW OF AFFECTED AREAS
  - 2.4. PROPOSED IRRIGATION EQUIPMENT INCLUDING:

- 2.4.1.1. CONTROLLERS AND WIRING AND/OR CONNECTIONS TO EXISTING
- 2.4.1.2. POINT OF CONNECTIONS WITH SIZE
- 2.4.1.3. VALVES INCLUDING MAKE, MODEL AND SIZE
- 2.4.1.4. IRRIGATION MANIFOLDS AND LATERALS WITH SIZES
- 2.4.2. IRRIGATION HEADS INCLUDING MAKE, MODEL, AND SIZE
- 2.4.3. VALVE BOXES AND EQUIPMENT INCLUDING PRESSURE RELEASE VALVES, SHUT-OFF VALVES AND QUICK COUPLING VALVES
- 2.4.4. GALLONAGE AND WATERING WINDOW OF AFFECTED AREAS
- 2.5. IRRIGATION PLANS SHALL BE DESIGNED BY THE IRRIGATION CONTRACTOR AND APPROVED BY THE OWNER'S REPRESENTATIVE AND OWNER PRIOR TO CONSTRUCTION.

3. COORDINATE DESIGNED IRRIGATION NEEDS WITH AVAILABILITY OF WATER FROM SOURCE INCLUDING TIMES AND/OR DATES WATER IS AVAILABLE. VERIFY CONTROLLER NEEDS PRIOR TO SYSTEM DESIGN.

4. COORDINATE LOCATION OF CONTROLLER WITH DRAIN VALVE. DESIGN ALLOWS FOR ACCURATE DRAINAGE OF SYSTEM AND EASIER FOR COMPLETE DISMANTLING OF SYSTEM. CONTRACTOR SHALL CONSIDER THE NEED FOR CHECK VALVES IN HEADS TO RESTRICT LOW HEAD DRAINAGE IN SYSTEM.
5. CONTRACTOR SHALL COORDINATE WITH ELECTRICAL CONTRACTOR. ELECTRICAL WIRING SHALL BE INSTALLED ACCORDING TO LOCAL CODE. THE COST OF ALL ELECTRICAL WORK NECESSARY TO MAKE THE AUTOMATIC IRRIGATION SYSTEM OPERATIONAL SHALL BE INCLUDED IN THE CONTRACTOR'S BID.

6. SYSTEM DESIGN SHALL FOLLOW INDUSTRY DESIGN STANDARDS, INCLUDING TO SIZE PIPE TO MANTAIN LESS THAN 5 FPS VELOCITY. USE A MINIMUM PIPE SIZE OF 3/4". SLEEVE ALL PIPE UNDER PAVING, WALKS AND ROADWAYS, MINIMUM SLEEVE LENGTH SHALL BE 12" ON EACH SIDE OF THE PIPE. CONTRACTOR SHALL BE RESPONSIBLE FOR PROPER OPERATION AT ALL SPRINKLER HEADS, LOCATE VALVES IN VALVE BOXES NEXT TO WALKWAYS OR OTHER ACCESSIBLE AREAS. CONTRACTOR SHALL NOT DAMAGE PAVING, WALKS, OR ROADWAYS DURING CONSTRUCTION.

7. BEFORE PROCEEDING WITH ANY WORK, THE CONTRACTOR SHALL INSPECT THE SITE, LOCATE ANY EXISTING IRRIGATION SYSTEM AND OTHER CONSTRUCTION, CHECK ALL GRADES AND VERIFY ALL DIMENSIONS AND CONDITIONS AFFECTING THE WORK IN ORDER TO PROCEED SAFELY.

8. PRIOR TO CONSTRUCTION, CONTRACTOR SHALL REPORT TO THE LANDSCAPE ARCHITECT OR OWNER ALL DEVIATION AND CHANGES FROM THE DESIGN AS ACCORDING TO THE CONTRACTOR'S DESIGN. SUBMIT A COPY TO OWNER, OWNER'S REPRESENTATIVE, AND MAINTENANCE STAFF UPON COMPLETION.

9. THE WORK (WHETHER MENTIONED OR NOT) SHALL CONSIST OF ALL LAB, TOOLS, MATERIALS, TEST, PERMITS AND OTHER EXPENSES NECESSARY TO MAKE THE AUTOMATIC IRRIGATION SYSTEM OPERATIONAL.

10. CONTRACTOR MUST BE A BONDED SPRINKLER IRRIGATION CONTRACTOR. THE SPRINKLER IRRIGATION SYSTEM MUST BE SUPERVISED BY A SPRINKLER IRRIGATION TECHNICIAN WITH FIVE (5) YEARS OR MORE OF EXPERIENCE. ALL ELEMENTS OF THE SYSTEM SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS.

11. PRIOR TO CONSTRUCTION, CONTRACTOR SHALL REPORT TO THE LANDSCAPE ARCHITECT OR OWNER ALL DEVIATION AND CHANGES FROM THE DESIGN AS ACCORDING TO THE CONTRACTOR'S DESIGN. SUBMIT A COPY TO OWNER, OWNER'S REPRESENTATIVE, AND MAINTENANCE STAFF UPON COMPLETION.

12. CONTRACTOR'S STANDBY ONE YEAR WARRANTY SHALL INCLUDE THE FOLLOWING:


- A. JETTING AND REPAIRS TO EXISTING SPRINKLER HEADS DUE TO SETTLEMENT OF IRRIGATION TRENCHES

- B. SYSTEM CAN BE ADEQUATELY DRAINED AND BLOWN OUT TO PROTECT FROM FREEZE DAMAGE.

- C. SYSTEM HAS BEEN ADJUSTED TO SUPPLY PROPER COVERAGE OF AREAS TO RECEIVE WATER.

**LAMP  
RYNEARSON**

14710 W. DODGE RD. STE. 100  
OMAHA, NE 68154  
402.466.4608  
LampRynearson.com



PRELIMINARY

NOT RELEASED FOR CONSTRUCTION

ZACHARY R. FERGUS

LA-007

IRRIGATION MAP

**811**  
ALL UTILITIES ARE SHOWN  
BASED ON INFORMATION PROVIDED  
BY THE OWNER. THE LOCATION OF  
THESE UTILITIES IS NOT GUARANTEED.  
THE USE OF EXCAVATION  
METHODS OTHER THAN  
TRENCHING IS  
NOT RECOMMENDED.  
ALL UTILITIES AND SERVICE  
LINES ARE THE PROPERTY OF  
THE OWNER OR PROVIDER.  
EXCAVATION  
MAY DAMAGE THESE UTILITIES.

Know where it is.  
Call before you dig.

811

DESIGNER / DRAFTER

ZACHARY R. FERGUS

DATE

JANUARY 3, 2022


PROJECT NUMBER

0120015.01-026/027

BOOK AND PAGE

SHEET

L3.0





ECHO PARK APARTMENTS - Building Five



1 NORTH ELEVATION

SCALE: 1/16" = 1'-0"



2 EAST ELEVATION

SCALE: 1/16" = 1'-0"



3 SOUTH ELEVATION

SCALE: 1/16" = 1'-0"



4 WEST ELEVATION


SCALE: 1/16" = 1'-0"

January, 2022

sinclairhille.com


AS200

© Copyright SINCLAIR HILLE ARCHITECTS



1 ROOF PLAN

SCALE: 1/16" = 1'-0"



TRASH ENCLOSURE

# ECHO HILLS REPLAT 5

LOT 1

## SARPY COUNTY, NEBRASKA



thompson, dreessen & dorner, inc.  
10836 Old Mill Rd  
Omaha, NE 68154  
p.402.330.8860 www.td2co.com

Project Name

## Exhibit C



**VICINITY MAP**

1. EXISTING ZONING IS GENERAL COMMERCIAL AND HIGH DENSITY RESIDENTIAL (C-1 AND C-2 COMMERCIAL CORRIDOR). PROPOSED ZONING IS P-1 AND C-3 COMMERCIAL CORRIDOR.
2. EXISTING AND PROPOSED CONTOURS ARE SHOWN AT 2 FT. INTERVALS.
3. WATER SHALL BE PROVIDED BY METROPOLITAN UTILITIES DISTRICT.
4. GAS SHALL BE PROVIDED BY THE BLACK HILLS ENERGY.
5. POWER SHALL BE PROVIDED FROM THE OMAHA PUBLIC POWER DISTRICT.
6. TYPICAL UTILITY EASEMENTS WILL BE DEDICATED WITH THE FINAL PLAT.
7. LOT REPLAT 4 IS NOT INCLUDED IN THIS REPLAT AND IS SHOWN FOR INFORMATIONAL PURPOSES ONLY.

PROPERTY OWNER

ECHO HILLS APARTMENTS LLC  
129 N 10TH STREET UNIT 106  
LINCOLN, NE 68508  
PHONE: 402-826-9393

## SUBDIVIDER

ECHO HILLS APARTMENTS LLC  
129 N 10TH STREET UNIT 106  
LINCOLN, NE 68508  
PHONE: 402-826-9393

ENGINEER

THOMPSON, DREESSEN & DORNER  
10836 OLD MILL ROAD  
OMAHA, NEBRASKA 68154  
PHONE: 402-732-8860

LEGAL DESCRIPTION

LEGAL DESCRIPTION

## LEGEND

Revision Dates		
No.	Description	MM-DD-YY
1	Initial	01-01-00
2	Minor Update	01-02-00
3	Major Revision	01-03-00
4	Minor Update	01-04-00
5	Major Revision	01-05-00
6	Minor Update	01-06-00
7	Major Revision	01-07-00
8	Minor Update	01-08-00
9	Major Revision	01-09-00
10	Minor Update	01-10-00
11	Major Revision	01-11-00
12	Minor Update	01-12-00
13	Major Revision	01-13-00
14	Minor Update	01-14-00
15	Major Revision	01-15-00
16	Minor Update	01-16-00
17	Major Revision	01-17-00
18	Minor Update	01-18-00
19	Major Revision	01-19-00
20	Minor Update	01-20-00
21	Major Revision	01-21-00
22	Minor Update	01-22-00
23	Major Revision	01-23-00
24	Minor Update	01-24-00
25	Major Revision	01-25-00
26	Minor Update	01-26-00
27	Major Revision	01-27-00
28	Minor Update	01-28-00
29	Major Revision	01-29-00
30	Minor Update	01-30-00
31	Major Revision	01-31-00
32	Minor Update	01-32-00
33	Major Revision	01-33-00
34	Minor Update	01-34-00
35	Major Revision	01-35-00
36	Minor Update	01-36-00
37	Major Revision	01-37-00
38	Minor Update	01-38-00
39	Major Revision	01-39-00
40	Minor Update	01-40-00
41	Major Revision	01-41-00
42	Minor Update	01-42-00
43	Major Revision	01-43-00
44	Minor Update	01-44-00
45	Major Revision	01-45-00
46	Minor Update	01-46-00
47	Major Revision	01-47-00
48	Minor Update	01-48-00
49	Major Revision	01-49-00
50	Minor Update	01-50-00
51	Major Revision	01-51-00
52	Minor Update	01-52-00
53	Major Revision	01-53-00
54	Minor Update	01-54-00
55	Major Revision	01-55-00
56	Minor Update	01-56-00
57	Major Revision	01-57-00
58	Minor Update	01-58-00
59	Major Revision	01-59-00
60	Minor Update	01-60-00
61	Major Revision	01-61-00
62	Minor Update	01-62-00
63	Major Revision	01-63-00
64	Minor Update	01-64-00
65	Major Revision	01-65-00
66	Minor Update	01-66-00
67	Major Revision	01-67-00
68	Minor Update	01-68-00
69	Major Revision	01-69-00
70	Minor Update	01-70-00
71	Major Revision	01-71-00
72	Minor Update	01-72-00
73	Major Revision	01-73-00
74	Minor Update	01-74-00
75	Major Revision	01-75-00
76	Minor Update	01-76-00
77	Major Revision	01-77-00
78	Minor Update	01-78-00
79	Major Revision	01-79-00
80	Minor Update	01-80-00
81	Major Revision	01-81-00
82	Minor Update	01-82-00
83	Major Revision	01-83-00
84	Minor Update	01-84-00
85	Major Revision	01-85-00
86	Minor Update	01-86-00
87	Major Revision	01-87-00
88	Minor Update	01-88-00
89	Major Revision	01-89-00
90	Minor Update	01-90-00
91	Major Revision	01-91-00
92	Minor Update	01-92-00
93	Major Revision	01-93-00
94	Minor Update	01-94-00
95	Major Revision	01-95-00
96	Minor Update	01-96-00
97	Major Revision	01-97-00
98	Minor Update	01-98-00
99	Major Revision	01-99-00
100	Minor Update	01-100-00

Drawn By: TDV Reviewed By: JAD  
Job No.: 2142-103 Date: 02-25-22

# Paving Improvements

## Exhibit D


Client Name  
**Echo Hills Apartments LLC**

Professional Seal


Revision Dates


No.	Description	MM-DD-YY
1		
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		
21		
22		
23		
24		
25		
26		
27		
28		
29		
30		
31		
32		
33		
34		
35		
36		
37		
38		
39		
40		
41		
42		
43		
44		
45		
46		
47		
48		
49		
50		
51		
52		
53		
54		
55		
56		
57		
58		
59		
60		
61		
62		
63		
64		
65		
66		
67		
68		
69		
70		
71		
72		
73		
74		
75		
76		
77		
78		
79		
80		
81		
82		
83		
84		
85		
86		
87		
88		
89		
90		
91		
92		
93		
94		
95		
96		
97		
98		
99		
100		
101		
102		
103		
104		
105		
106		
107		
108		
109		
110		
111		
112		
113		
114		
115		
116		
117		
118		
119		
120		
121		
122		
123		
124		
125		
126		
127		
128		
129		
130		
131		
132		
133		
134		
135		
136		
137		
138		
139		
140		
141		
142		
143		
144		
145		
146		
147		
148		
149		
150		
151		
152		
153		
154		
155		
156		
157		
158		
159		
160		
161		
162		
163		
164		
165		
166		
167		
168		
169		
170		
171		
172		
173		
174		
175		
176		
177		
178		
179		
180		
181		
182		
183		
184		
185		
186		
187		
188		
189		
190		
191		
192		
193		
194		
195		
196		
197		
198		
199		
200		
201		
202		
203		
204		
205		
206		
207		
208		
209		
210		
211		
212		
213		
214		
215		
216		
217		
218		
219		
220		
221		
222		
223		
224		
225		
226		
227		
228		
229		
230		
231		
232		
233		
234		
235		
236		
237		
238		
239		
240		
241		
242		
243		
244		
245		
246		
247		
248		
249		
250		
251		
252		
253		
254		
255		
256		
257		
258		
259		
260		
261		
262		
263		
264		
265		
266		
267		
268		
269		
270		
271		
272		
273		
274		
275		
276		
277		
278		
279		
280		
281		
282		
283		
284		
285		
286		
287		
288		
289		
290		
291		
292		
293		
294		
295		
296		
297		
298		
299		
300		
301		
302		
303		
304		
305		
306		
307		
308		
309		
310		
311		
312		
313		
314		
315		
316		
317		
318		
319		
320		
321		
322		
323		
324		
325		
326		
327		
328		
329		
330		
331		
332		
333		
334		
335		
336		
337		
338		
339		
340		
341		
342		
343		
344		
345		
346		
347		
348		
349		
350		
351		
352		
353		
354		
355		
356		
357		
358		
359		
360		
361		
362		
363		
364		
365		
366		
367		
368		
369		
370		
371		
372		
373		
374		
375		
376		
377		
378		
379		
380		
381		
382		
383		
384		
385		
386		
387		
388		
389		
390		
391		
392		
393		
394		
395		
396		
397		
398		
399		
400		
401		
402		
403		
404		
405		
406		
407		
408		
409		
410		
411		
412		
413		
414		
415		
416		
417		
418		
419		
420		
421		
422		
423		
424		
425		
426		
427		
428		
429		
430		
431		
432		
433		
434		
435		
436		
437		
438		
439		
440		
441		
442		
443		
444		
445		
446		
447		
448		
449		
450		
451		
452		
453		
454		
455		
456		
457		
458		
459		
460		
461		
462		
463		
464		
465		
466		
467		
468		
469		
470		
471		
472		
473		
474		
475		
476		
477		
478		
479		
480		
481		
482	</td	


# Exhibit E














### IRRIGATION NOTES


1. THE CONTRACTOR SHALL MIGRATE THE EXISTING IRRIGATION SYSTEM, AS NECESSARY, WHILE MAINTAINING FUNCTIONALITY OF THE SYSTEM. AT ALL TIMES, THE CONTRACTOR CONSTRUCTS, MODIFIES AND MAINTAINS THE EXISTING SYSTEM, INCLUDING REMOVING AND RELOCATING EXISTING SYSTEMS, PLACEMENT OF NEW SYSTEMS, AND THE REMOVAL OF EXISTING EQUIPMENT, BOXES, AND OTHER IRRIGATION SYSTEM COMPONENTS TO MAINTAIN FUNCTIONALITY OF THE SYSTEM THROUGH ALL UNDERTAKINGS, INCLUDING, BUT NOT LIMITED TO, THE REMOVAL AND RELOCATION OF EXISTING EQUIPMENT.
2. THE CONTRACTOR, AT COMPLETION OF CONSTRUCTION OR DURING LANDSCAPE OPERATIONS, SHALL MODIFY THE IRRIGATION SYSTEM TO PROVIDE COVERAGE ACROSS ALL IRRIGATED SOIL AND TO PREVENT SPRINKLER HEADS FROM PUMPING OVER ANY PAVED SURFACE.
3. IRRIGATION SYSTEMS TO PROVIDE GO-BUILD IRRIGATION SYSTEM IN AREAS AS INDICATED. IRRIGATION SYSTEM DRAWINGS SHALL BE SUBMITTED TO THE ARCHITECT/ENGINEER AND OWNER FOR THEIR RECORDS.
4. ALL SODDED AREAS, PLANTING REEFS, AND ISLANDS (WITHIN THE LIMITS OF THE PROJECT) SHALL BE IRRIGATED. CONTRACTOR SHALL REFER TO "LIMITS OF IRRIGATION" – THIS SHEET.
5. CONTRACTOR TO COORDINATE LOCATION OF EXISTING VALVES, TIMERS AND HEADS WITH OWNER.

## IRRIGATION SPECIFICATION

1. WITHIN THE LIMITS OF THE PROPOSED LANDSCAPED AREAS SHOWN ON THIS PLAN, CONTRACTOR SHALL PROVIDE A FULLY AUTOMATIC OPERATIONAL IRIGATION SYSTEM. THE COMPLETED PRESSURIZED SYSTEM (INCLUDING PIPE, VALVES, PUMPS, BACKFLOW PREVENTER, DRAIN VALVE, MANIFOLD, VALVES, LATERALS, HEADS, CONTROLLER, AND WIRING) SHALL NOT OVERSPRAY INTO ANY PUBLIC HIGHWAY, ROAD, STREET, OR PROPERTY OWNED BY THE STATE, MUNICIPAL, SRI, OR OTHER. THE SYSTEM SHALL NOT OVERSPRAY INTO WAHS, PARKS, OR BUILDINGS AND SHALL TAKE DUE CONSIDERATION WHEN CALCULATING FOR THE POTENTIAL FOR OVERSPRAY. THE UNDERGROUND SYSTEM SHALL NOT OVERSPRAY INTO WAHS, PARKS, OR BUILDINGS. THE SYSTEM SHALL NOT OVERSPRAY INTO HEADS, VALVES, PIPING, FITTINGS, CONTROLLERS, WIRING, ETC., OF SIZES AND TYPES APPROPRIATE FOR THE AREAS SHOWN AND MEETING ALL APPLICABLE CODES AND MANUFACTURER'S RECOMMENDATIONS. ALL EQUIPMENT SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS AND STANDARD INSTALLATION PRACTICES. FINISHED IRIGATION SYSTEM SHALL COMPLY WITH LOCAL PLUMBING CODE.

LAMP

14710 W. DODGE RD, STE. 1  
OMAHA, NE 68154  
402.496.2498  
[LampRynearson.com](http://LampRynearson.com)



PRELIMINARY

NOT RELEASED FOR CONSTRUCTION  
ZACHARY R. FERGUS

ECHO HILLS APARTMENTS  
1A VISTA NEBRASKA



Know what's below.  
Call before you dig.

**DESIGNER / DRAFTER**  
**ZACHARY R. FERGUS**  
**DATE**  
**JANUARY 3, 2022**  
**PROJECT NUMBER**  
**0120015.01-026/027**  
**BOOK AND PAGE**


L3.0

**Echo Hills  
144<sup>th</sup> & Echo Hills Drive  
La Vista, Nebraska  
LAV-20200408-5420**

**DRAINAGE STUDY  
May 2020  
(Revised March 2022)**



Prepared By: \_\_\_\_\_  
Trevor D. Veskna, P.E.



**DRAINAGE STUDY & PCSMP CALCULATIONS****Echo Hills**144<sup>th</sup> & Echo Hills Drive  
La Vista, NE**TABLE OF CONTENTS**

1. SITE CHARACTERISTICS.....	3
2. RUNOFF ANALYSIS.....	4
3. STORMWATER CONVEYANCE DESIGN.....	7
4. STORMWATER BEST MANAGEMENT PRACTICES (BMP) DESIGN.....	8
5. PERMITS.....	10
APPENDIX.....	11
DM-1 Existing Drainage Map.....	12
DM-2 Proposed Drainage Map.....	13
C7.0 Storm Sewer Plan and Profile.....	14
C7.1 Roof Drain Plan.....	15
C7.2 Roof Drain Plan.....	16
C7.3 Storm Sewer Reroute.....	17
C10.0 Post-Construction Stormwater Management Plan.....	18
OFFSITE DRAINAGE AREA.....	19
CULVERT AND DITCH ANALYSIS.....	20
CALCULATIONS.....	23
PIPE CALCULATIONS.....	24
DRAINAGE AREA CALCULATIONS.....	25
NYLOPLAST INLET CAPACITY.....	26
HYDROGRAPH REPORT.....	29
POND REPORTS.....	32
FLEX-A-MAT SIZING.....	36
USADA SOIL REPORT.....	37

## **DRAINAGE STUDY AND PCSMP CALCULATIONS**

Echo Hills  
144<sup>th</sup> & Echo Hills Drive  
La Vista, NE  
LAV-20200408-5420

### **EXECUTIVE SUMMARY**

This drainage study was prepared for a development located at 144<sup>th</sup> & Echo Hills Drive, La Vista, Nebraska. This study will identify and analyze solutions to stormwater runoff and water quality treatment associated with this development.

The total area of this site is 12.43 acres, with the approximately 12.43 acres being disturbed in this development. The proposed development will consist of constructing multi-family apartment buildings, an assisted living facility, grading, paving, and utilities to service the site.

The stormwater facility used for storm water detention and treatment will be an extended dry detention basin. The basin was designed to meet the City of La Vista stormwater specifications and standards.

#### **1. Site Characteristics**

##### **A. Pre-development Conditions**

The existing conditions can be seen on DM-1, found in the Appendix of this report. The topographic survey and aerial photographs obtained from Sarpy County GIS was used to determine the existing conditions and impervious coverage. This site is located northwest of 144<sup>th</sup> Street (Highway 50) and Chandler Road. Echo Hills Drive abuts to the north, 144<sup>th</sup> Street (Highway 50) to the east, Chandler Road to the south, and 146<sup>th</sup> Street to the west. Beyond the abutting streets, there are residential homes to the north and west, a storage facility to the east, and an undeveloped lot zoned I-1 to the south. The site was previously used for agriculture and is currently zoned C-1 with a Gateway Corridor Overlay.

Per the Geotechnical Report prepared by TD2 dated March 31, 2020, the site consists of natural Peoria loess overlying Loveland loess. The USDA classifies these soils as Hydrologic Soil Group C with infiltration rates ranging between 0.20 to 0.60 in/hr. A copy of the USDA Soil Report can be found in the Calculations Section.

The site is split into three main drainage areas (EX-1 through EX-3) with three impact points. Runoff from area EX-1 overland flows to the south, offsite to an existing drainage swale at Impact Point 1. Runoff from area EX-2 overland flows to the southeast and is collected by existing curb inlets along 144<sup>th</sup> Street at Impact Point 2. Runoff from area EX-3 overland flows to an existing curb inlet along 146<sup>th</sup> Street at Impact Point 3, then is routed to Impact Point 1 via storm sewers and discharges at the existing flared end section.

##### **B. Post-development Conditions**

The proposed conditions can be seen on DM-2, in the Appendix. The development will consist of multi-family apartments, an assisted living facility, parking areas, paved drives, and sidewalks, resulting in an increase in impervious area for the entire site from 0% to 65%.

The proposed site will consist of 3 main drainage areas, each sub-divided into individual drainage catchments.

Areas A1.1 – A1.14 will be collected by the proposed storm sewer system and routed to the extended dry detention basin, EDDB-1, at Impact Point 1.

Runoff from areas A2.1 – A2.4 will be collected by the proposed storm sewer system, roof drains, and overland flow to the two basins located to the south and west of the assisted living facility. These basins are intended to provide detention rather than treatment; however, it can be expected that some treatment will be provided through vegetative flow within the basins. Following detention, the runoff from these areas will be routed to the extended dry detention basin at Impact Point 1.

Areas B1.1 – B1.4 will not be captured by the proposed storm sewer system and will overland flow offsite. Area B1.1 will overland flow offsite to the west to Impact Point 3. Areas B1.2 and B1.4 will overland flow offsite and ultimately reach Impact Point 1 to the south. Area B1.3 will overland flow offsite to the east and be collected by the existing curb inlets along 144<sup>th</sup> Street at Impact Point 2.

#### **C. Contributing Off-site Drainage**

Due to the existing site conditions and based on the contours obtained during TD2's topographical survey, no off-site drainage is expected to flow onto the site.

#### **D. Floodways, Floodplains, and Wetlands**

The site does not contain any floodways, floodplains, or known wetlands.

### **2. Runoff Analysis**

#### **A. Pre-Development Runoff Analysis**

##### **i. Watershed Area:**

Information for the existing drainage areas can be found in Table 1 below. Area EX-1 overland flows to the south towards Impact Point 1. Area EX-2 overland flows to the east onto 144<sup>th</sup> Street and is collected by existing curb inlets at Impact Point 2. Area EX-3 overland flows to the west onto 146<sup>th</sup> Street and is collected by an existing curb inlet at Impact Point 3.

##### **ii. Time of Concentration:**

For area EX-1, the time of concentration was calculated to be 6.2 minutes using Hydroflow Hydrographs Extension for AutoCAD 2020, TR-55 method. For areas EX-2 and EX-3, the time of concentration was calculated to be less than 5 minutes. A minimum value of 5 minutes will be used for these drainage areas.

##### **iii. Precipitation Model:**

The rainfall intensity duration frequency (IDF) curve for Omaha for the 2, 10, 50, and 100-year, 24-hour storm was used.

##### **iv. Runoff Coefficient:**

The existing lot primarily consists of agricultural land used for farming. The breakdown of these areas can be found in the Drainage Area Calculations table in the Calculations Section of

this report. The CN and C values were obtained using the Omaha Regional Stormwater Design Manual, Chapter 2, for straight row crops in the Hydrologic Soil Group C. These values are listed in Table 1 below.

**Table 1. Existing Drainage Areas**

ID	Total Area (Ac.)	Total Area (SF)	Composite C	Composite CN	Impact Point	Tc (min.)
EX-1	9.17	399,243	0.25	85	1	6.2
EX-2	3.06	133,491	0.25	85	2	5.0
EX-3	0.20	8,896	0.25	85	3	5.0
<b>Total</b>	<b>12.43</b>	<b>541,630</b>	<b>0.25</b>	<b>85</b>		

**v. Runoff Model:**

The SCS (Type II) method was used to calculate the runoff and peak discharge for the existing site.

**vi. Summary of Pre-development Runoff:**

Information for the pre-development runoff can be found in Table 2 below.

**Table 2. Existing Runoff Values**

Pre-Construction	2 Year (cfs)	10 Year (cfs)	50 Year (cfs)	100 Year (cfs)
Impact Point 1	24.55	45.50	64.07	73.35
Impact Point 2	8.18	15.15	21.33	24.42
Impact Point 3	0.53	0.99	1.39	1.60
<b>Total</b>	<b>33.26</b>	<b>61.64</b>	<b>86.79</b>	<b>99.37</b>

**B. Post-Development Runoff Analysis**

**i. Watershed Area:**

The proposed site is divided into three main drainage categories. Runoff from areas A1.1 – A1.14 will remain onsite and be collected by the proposed storm sewer and routed to the extended dry detention basin, EDDB-1. Runoff from areas A2.1 – A2.4 will remain onsite and first be detained in the two basins located south of the assisted living before being routed to EDDB-1. Runoff from areas B1.1 – B1.4 will not be collected by the proposed storm sewer system and will instead overland flow offsite to Impact Points 1, 2, and 3. Information for each area can be seen in Table 3 on the next page.

**ii. Time of Concentration:**

The time of concentration for each proposed drainage area was determined to be 5 minutes using the Hydroflow Hydrographs Extension for AutoCAD 2020, TR-55 method.

**iii. Precipitation Model:**

The rainfall intensity duration frequency (IDF) curve for Omaha for the 2, 10, 50, and 100-year, 24-hour storm was used as the precipitation model.

**iv. Runoff Coefficient:**

The proposed development will consist of areas of pavement, buildings, grass, and landscaped areas. The breakdown of these areas can be found in the Drainage Area Calculations table in the Calculations Section of this report. The CN and C values were obtained using the Omaha Regional Stormwater Design Manual, Chapter 2, for open spaces and pavement, all in the Hydrologic Soil Group C.

The total proposed site will have a combined CN value of 90 and a combined C value 0.76. These values have increased compared to existing conditions due to the increase in impervious coverage, but the runoff will decrease for each storm event due to the storage provided by the proposed extended dry detention basin. The storage provided by the basin will be discussed later in this report. Runoff coefficients for each area are listed in Table 3 below.

**Table 3. Proposed Drainage Areas**

ID	Description	Total Area (Ac.)	Total Area (SF)	Composite C	Composite CN	Impact Point	Tc (min.)
A1.1	Parking Area	0.22	9,419	0.69	87	1	5
A1.2	Parking Area & Building 1	0.45	19,479	0.92	97	1	5
A1.3	Parking Area	0.75	32,618	0.87	94	1	5
A1.4	Parking Area & Building 4	0.60	26,260	0.93	97	1	5
A1.5	Parking Area	0.19	8,211	0.94	98	1	5
A1.6	Parking Area	0.16	7,137	0.82	92	1	5
A1.7	Basin Area	0.36	15,724	0.44	76	1	5
A1.8	Parking Area	0.63	27,477	0.82	92	1	5
A1.9	Parking Area & Building 5	0.73	31,686	0.88	95	1	5
A1.10	Parking Area	0.45	19,673	0.82	92	1	5
A1.11	Parking Area	0.90	39,259	0.91	96	1	5
A1.12	Parking Area	0.27	11,613	0.95	98	1	5
A1.13	Parking Area	0.44	19,298	0.80	91	1	5
A1.14	Building 5 Area	0.46	20,199	0.81	91	1	5
A2.1	Assisted Living	1.54	67,136	0.63	84	1	5
A2.2	Parking Area	0.43	18,574	0.81	92	1	5
A2.3	Parking Area	0.64	27,676	0.87	95	1	5
A2.4	Assisted Living	1.62	70,492	0.78	90	1	5
B1.1	West Offsite	0.20	8,639	0.40	74	3	5
B1.2	West Offsite	0.44	19,002	0.53	80	1	5
B1.3	East Offsite	0.53	22,925	0.45	75	2	5
B1.4	South Offsite	0.52	22,552	0.76	90	1	5
	Total	12.43	541,630	0.76	90		

**v. Runoff Model:**

The SCS (Type II) method was used to calculate the runoff and peak discharge for the proposed site.

vi. **Summary of Post-development Runoff:**

The post-development and pre-development runoff values are shown in Table 4 below. Using the proposed BMPs, the post-development runoff will be reduced at each Impact Point.

**Table 4. Pre vs. Post Construction Runoff**

Impact Point 1	2 Year (cfs)	10 Year (cfs)	50 Year (cfs)	100 Year (cfs)
Pre-Construction	24.55	45.50	64.07	73.35
Post Construction	23.08	41.14	52.95	59.62
Impact Point 2	2 Year (cfs)	10 Year (cfs)	50 Year (cfs)	100 Year (cfs)
Pre-Construction	8.18	15.15	21.33	24.42
Post-Construction	0.96	2.12	3.25	3.83
Impact Point 3	2 Year (cfs)	10 Year (cfs)	50 Year (cfs)	100 Year (cfs)
Pre-Construction	0.53	0.99	1.39	1.60
Post-Construction	0.31	0.69	1.07	1.27

**3. Stormwater Conveyance Design:**

**A. Design Information References:**

All stormwater conveyance systems have been designed in accordance with the Omaha Regional Stormwater Design Manual, Current Edition.

**B. Storm Sewer:**

- i. The Rational Method was used for pipe sizing calculations. The storm sewers were designed to have the capacity to adequately transfer the 10-year peak 24-hour design storm. The hydraulic grade lines for the proposed storm sewer system can be found in the Calculations section of the Appendix.
- ii. The storm sewer inlets were designed and sized to adequately handle the 10-year peak 24-hour storm events. Storm sewer inlet capacity tables can be found in the Calculations section of the Appendix.

**C. Open Channel Flow – Swales and Ditches: Highway 50 Roadside Ditch Capacity**

The existing ditch and 60" flared end section (FES) located at the south end of the site (north of Chandler Road) was analyzed for capacity. It is our intent to show the project will do the following items:

- Will not divert existing drainage in Right of Way or off-site, upstream areas from its natural, established drainage basin
- Will not allow drainage waters from upstream areas and this development to overtop or flow onto Chandler Road or Highway 50
- Post-development discharge rates will not exceed pre-development discharge rates (addressed in Section 2. vi. above)

Drainage Map of the upstream areas, culvert analysis, inlet control analysis, and ditch capacity are included in the Appendix of this report.

The following design parameters were used:

- Manning's coefficient of 0.24 for dense grass
- Elevation 1077 used for bottom of ditch
- Elevation 1085 used for top of ditch
- 60" FES invert elevation = 1075.69 (from topo)
- Ditch width = 8'
- Side slopes = 3:1
- Ditch slope = 0.96%
- $Q_{50} = 160 \text{ cfs}$  (111 cfs upstream and 49 cfs from development per Hydraflow)

Analysis from Hydraflow calculated the water level for the 50 year storm to be approximately 1082.3. Using **Exhibit F.1 Headwater Depth for Concrete Pipe Culverts with Inlet Control**, from *the Nebraska Department of Transportation – Drainage Design and Erosion Control Manual*, August 2006, Page F-3, the ponding depth of the ditch is 5.65'. Using the FES I.E. of 1075.69 and adding 2' of free board, the final height of the headwater was 1083.34. The lowest elevation of Chandler Road along this ditch is approximately 1086, hence the inlet control of the 60" FES will not negatively affect the capacity of the roadside ditch.

**D. Extended Dry Detention Basin Discharge and Energy Dissipation:**

The flow at the basin outlet pipe for the 50-year storm event is calculated at 49.55 cfs. For the 30" R.C.P. outlet pipe, a 10' x 12' section of Flex-A-Mat will be used to dissipate energy and help prevent erosion. The Flex-A-Mat sizing sheet has been included in the calculations portion of this report.

**E. Hydraulic Model:**

Hydraflow Hydrographs Extension for AutoCAD 2020 was used to model the existing and post-development runoff conditions.

**4. Stormwater Best Management Practices (BMP) Design:**

**A. Design Standards:**

All stormwater facilities were designed in accordance with the Omaha Regional Stormwater Design Manual, Current Edition, and City of La Vista code.

**B. Extended Dry Detention Basin (EDDB) Location:**

The proposed extended dry detention basin is in the southwest corner of the site. Per the Geotechnical Report prepared by TD2, free standing groundwater was not encountered in any of the boring locations; therefore, groundwater should not interfere with the proposed basin.

### C. Detention System Performance:

The total disturbed area for the development is approximately 12.43 acres, resulting in a water quality volume of 22,567 C.F. Using the cascading planes concept for the northwest portion of the site (A2.1 – A2.4), approximately 2.61 acres of impervious area flows to 1.47 acres of pervious area. This results in a reduction of the water quality treatment volume from 0.50 inch to 0.42 inch for area A2.1, and 0.47 inch for areas A2.2 – A2.4. The new total water quality volume for the site is reduced to 20,025 C.F. The proposed extended dry detention basin (EDDB-1) has a treatment volume of approximately 20,559 C.F. and can detain and release this volume over a period of 24-hours. See Table 5 for the EDDB elevations and release rates.

**Table 5. Extended Dry Detention Basin**

	Stage	Elevation (Ft)	Total Storage (CF)	Inflow (CFS)	Outflow (CFS)	Comments
1	0.00	1082.00	0	0	0.00	Bottom of Basin
2	1.00	1083.00	2,455	-	0.12	
3	2.00	1084.00	5,505	-	0.17	
4	3.00	1085.00	9,200	-	0.22	
5	4.00	1086.00	13,600	-	0.25	
6	5.00	1087.00	18,765	-	0.28	
7	5.10	1087.30	20,559	-	-	Inlet Opening
8	5.92	1087.92	24,255	26.66	21.90	2-Year Event
9	6.00	1088.00	24,745	-	24.21	
10	6.71	1088.71	29,636	48.02	38.75	10-Year Event
11	7.00	1089.00	31,600	-	43.22	
12	7.56	1089.56	35,935	67.70	49.55	50-Year Event
13	7.99	1089.99	39,276	76.29	56.60	100-Year Event
14	8.00	1090.00	39,390	-	57.58	Top of Basin

### D. Detention System Outlet Structure

The outlet structure for the extended dry detention basin will be a 72" Type II Area Inlet with a 6" diameter orifice. In order to obtain the 24-hour drawdown time of the water quality treatment volume, the outlet structure will be fitted with a stainless-steel slide valve at the 6" orifice. The slide valve will be positioned so that the equivalent 24-hour drawdown orifice area is achieved. The Post Construction Stormwater Management Plan, found in the Appendix section of this report, details the orifice area calculations.

## **E. Spillway and Embankment Protection**


The extended dry detention basin can retain the 50-year storm event without overtopping. If the outlet structure should become clogged or a larger storm event occurs, the basin will overflow to the existing drainage ditch at Impact Point 1. The side slopes of the basin will be permanently seeded and matted after upstream areas have been stabilized.

## **5. Permits**

The following permits will be needed for this project:

- City of La Vista Grading Permit and NPDES Permit - both have been filed with the City of La Vista through the Omaha Permix website and the Nebraska Department of Environment and Energy
- Nebraska Department of Transportation Permit to Perform Work on Public Right of Way for Storm Sewer Construction





**TD2**  
engineering  
& surveying

thompson, dreessen & dorner, inc.  
10836 Old Mill Rd  
Omaha, NE 68154  
p.402.330.8860 [www.td2co.com](http://www.td2co.com)

## Project Name

## Exhibit H

Client Name

Professional Sea

## Revision Dates


No.	Description	MM-DD-YY
1		
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		
21		
22		
23		
24		
25		
26		
27		
28		
29		
30		
31		
32		
33		
34		
35		
36		
37		
38		
39		
40		
41		
42		
43		
44		
45		
46		
47		
48		
49		
50		
51		
52		
53		
54		
55		
56		
57		
58		
59		
60		
61		
62		
63		
64		
65		
66		
67		
68		
69		
70		
71		
72		
73		
74		
75		
76		
77		
78		
79		
80		
81		
82		
83		
84		
85		
86		
87		
88		
89		
90		
91		
92		
93		
94		
95		
96		
97		
98		
99		
100		

Drawn By: TDV Reviewed By: JAD  
Job No.: 2142-103 Date: 02-25-22

Chart 7a

## Utility Plan

Sheet Number \_\_\_\_\_



# Exhibit I

Lot 1, Echo Hills Replat 4 and Lot 1, Echo Hills Replat 5  
**SEWER CONNECTION AGREEMENT**  
(Sanitary Sewer System)

THIS AGREEMENT, made and entered into in La Vista, Nebraska, on this \_\_\_\_\_ day of \_\_\_\_\_, \_\_\_\_\_, by and between the City of La Vista, a Municipal corporation in the State of Nebraska (hereinafter referred to as "City"), and Echo Hills Apartments LLC, and Echo Hills Almc LLC, (hereinafter referred to as "Owner");

WITNESSETH:

WHEREAS, the Owner has constructed or is contemplating constructing sanitary sewer services within Lot 1, Echo Hills Replat 4 and Lot 1, Echo Hills Replat 5, a subdivision, shown on Exhibit "A" hereto; and

WHEREAS, Owner desires to provide for the flow, transportation and handling of sewage collected in or flowing into the sanitary sewer services constructed or to be constructed by it, and has requested the City to permit flowage thereof into the City sewerage system, and to provide for the processing of such sewage.

NOW, THEREFORE, in consideration of the mutual agreements and covenants of the parties hereto, it is agreed by and between the parties as follows:

I

For the purposes of this Agreement, the term "sewer system of the Owner" shall include, whether now in existence or hereafter constructed, all sanitary sewers, sanitary sewer services and appurtenances thereto which are:

- A. Shown on Exhibit "B" attached hereto.

For the purposes of this Agreement, the following, whether now in existence or hereafter constructed, shall be deemed a part of the sewer system of the City:

- A. Any sanitary sewer or system of sanitary sewers owned by the City;
- B. Any sanitary sewer or system of sanitary sewers not a part of the sewer system of the Owner and not owned by City, but through which City has an easement, license or other right or other license to transport sanitary sewage;

II

Subject to the conditions and provisions hereinafter specified, the City hereby grants permission to the Owner to connect the sanitary sewer system of the Owner to the sanitary sewer system of the City in such manner and at such place or places as designated on plans submitted by the Owner and approved by the City.

III

Owner expressly promises, warrants, covenants and agrees:

- A. That the sewer system of the Owner will be constructed and, as required, reconstructed in strict accordance with the plans and specifications and location approved in writing by the City and in strict accordance with the minimum standards and requirements of construction adopted by City.
- B. That the sewer system of the owner shall be designed and constructed, and as required reconstructed, at the expense of Owner and the property therein and at no expense to the City.
- C. The sewer system of the Owner shall comply with all applicable Federal and State laws and regulations in general and with all applicable laws and regulations of the City, with reference to use, operation and maintenance of the system.
- D. The sewer system of the Owner shall at all times be properly maintained and kept in good operating order and repair at no cost to City. The Owner's obligation in this connection shall survive the term of this Agreement to the extent provided in Paragraph IV, infra.
- E. In the event that City's engineers find that there is anything in the construction, maintenance or operation of the sewer system of the Owner which will, in the opinion of City's engineers, be detrimental to the proper operation of the sewer system of City, or any part thereof, the Owner will, on notice thereof, promptly correct said defect.
- F. That in the event the Owner for any reason fails in any respect as to its covenants contained in this Paragraph III, then City may, at its option, perform such maintenance and repair or correct such defects and the Owner, upon written demand by City, shall promptly reimburse City for all work, services, materials and other expenses incurred or expended by City in connection therewith.
- G. At all times all sewage flowing into, passing through or from the sewer system of the Owner shall be in conformity with the ordinances, regulations and conditions applicable to sewage and sewers within the City, as they may change from time to time. In no event shall Owner, without prior written consent of City, permit or suffer any type of sewage to flow into, pass through or from the sewerage system of the Owner, in violation of such ordinances, regulations and conditions.
- H. In respect to any industrial use or connection to the sewer system of the Owner, the City may condition such approval upon such terms as it deems necessary to protect the sewer systems of the Owner and the City.

In furtherance of the foregoing, the Owner shall, whenever necessary, provide at their expense such preliminary treatment as may be necessary to meet the applicable ordinance, regulation or condition. Such preliminary treatment facilities shall be maintained continuously in satisfactory and effective operation at no expense to the City.

The Owner shall allow any duly authorized representative of City to enter upon such property at reasonable times for the purpose of inspection, observation, measurements, sampling and testing of sewage.

- I. The Owner shall not cause, suffer or permit to be connected to the sewer system of the Owner any sewer lines or sewers serving, directly or indirectly, any area outside its boundaries.
- J. That the Owner is, or at time of construction will be, the Owner of the entire proposed sanitary sewer system situated within its boundaries.
- K. That the Owner will indemnify and save harmless the City, its officers, employees and agents, from all construction costs, loss, damage, claims and liability of whatsoever kind or character due to or arising out of any acts, conduct, omissions or negligence of the Owner, its officers,

agents, employees, contractors, subcontractors and anyone acting under the direction of the Owner, in doing any work or construction of the sewer system of the Owner, or by or in consequence of any performance of this contract.

- L. That Owner shall promptly file all reports, pay all connection fees and perform all other obligations of the Owner provided for in this Agreement or otherwise required by state statutes or the City's ordinances as amended and supplemented from time to time.
- M. That, subject to the provisions of Paragraph V, infra, the Owner is and shall be bound to and by any provisions of any ordinance, rule or regulation relating to sewer use fees provided for under said Paragraph V, infra, hereinafter made and adopted by City or Sarpy County.
- N. Any water distribution system serving the Owner shall be constructed and operated by the Metropolitan Utilities District.

#### IV

The herein granted easements and licenses to City and the herein contained covenants of perpetual maintenance and repair by the Owner shall be perpetual, notwithstanding the fact that this Agreement is for a term of 20 years.

#### V

Owner further expressly promises, warrants, covenants and agrees that no connection shall be made to the sewer system of the City until a permit therefore shall have been obtained from City and the appropriate connection fee paid to City. Owner shall:

- A. Require the person, firm or entity to whose property the connection is being made to:
  - 1. pay to City the applicable sewer connection fees as prescribed by the ordinances of the City of La Vista in effect at the time of the connection;
  - 2. obtain from the City a permit to so connect, as may be required by the ordinances of the City of La Vista in effect at the time of the connection.
- B. Enter into agreements as shall be necessary to:
  - 1. assure the said obtaining of a permit from City and payment of connection fees to City;
  - 2. require the disconnection of any connection made to the sewer system of the City which shall have been made without the proper permit from the City and payment of connection fees to City;
  - 3. assure that all connections to the sewer system of the City will be made in accordance with applicable ordinances, regulations and specifications.
- C. Upon the demand of City, the Owner shall pay to City the amount of any connection fee owing City for any connection to the sewer system of the Owner or of the City which shall not have been previously paid to the City by the person, firm or entity to whose property the connection shall have been made.
- D. Upon notice by City, the Owner shall immediately cause to be disconnected any connection to the sewer system which has been made without the required permit from the City or which is in contravention of the ordinances, regulations or specifications of the City of La Vista pertaining to sewer connections.

## VI

The Owner shall facilitate collection of sewer service and sewer use fees as may be prescribed by City ordinance. Except as may be otherwise provided by City, such fees shall be based upon water consumption with chargeable water flow computed in the manner employed by Metropolitan Utilities District, which shall collect sewer service or use fees in conjunction with its collection of charges for water use.

## VII

In the event of the Owner's breach of any of the terms and conditions hereof or any warranty or covenant herein made by the Owner, then:

- A. In the case of a breach of any term or condition, warranty or covenant, pertaining to the actual construction, reconstruction, repair, maintenance or operation of the sewer system of the Owner, Owner shall, within five (5) days from receipt of City's notice of such breach, commence to take corrective measures or such measures as may be reasonably requested by the City, and the Owner shall pursue with due diligence such corrective measures to completion as soon thereafter as possible to the reasonable satisfaction of City.
- B. In the case of any other type of breach by the Owner, the Owner shall cure said breach to the reasonable satisfaction of City within thirty (30) days from receipt of City's notice of such breach; provided however, that if the nature of Owner's breach is such that more than thirty (30) days are reasonably required for its cure, then the Owner shall not be deemed to be in breach if the Owner commenced such cure within thirty (30) day period and thereafter diligently prosecutes such cure to completion.
- C. In the event the Owner shall fail to cure any breach within the applicable time and manner afore-prescribed, City may:
  1. Upon giving the Owner sixty (60) days notice of City's intent to do so, City may require the Owner to disconnect the sewer system of the Owner from the sewer system of the City, or the City may itself cause such disconnection to be made, if at the expiration of said sixty (60) day period the breach is not cured to the reasonable satisfaction of City. Any such disconnection shall be made at the expense of the Owner.
  2. In the event the breach pertains to the actual construction, reconstruction, repair, maintenance or operation of the sewer system of the Owner, City shall have the absolute right, at its option, to itself perform the work necessary for the requested corrective measures, or to complete the corrective measures commenced by the Owner, as the case may be, in either of which events the owner agrees:
    - (a) Owner shall immediately reimburse City for any and all expense incurred by City in connection therewith.
    - (b) Owner shall indemnify and hold harmless City, its officers, employees and agents, from any expenses, costs, claim, action, cause of action, or demand arising out of City's taking or completing said corrective measures.
  3. In addition to whatever other remedies are granted to City herein, City may avail itself of all other rights and remedies that City may have pursuant to any statute, law, or rule of law or equity, including, but not limited to the right to specifically enforce full compliance by the Owner of the terms and conditions of this Agreement, including all warranties and covenants and agreements herein made by the Owner, by both mandatory and prohibitory injunction.

## VIII

The term of this Agreement shall be twenty (20) years from and after date hereof; provided, however, that unless one of the parties hereto shall advise the other party in writing of its desire not to do so, this Agreement shall be automatically renewed on the same terms and conditions as herein set forth for additional successive terms of twenty (20) years each. Said written advice shall be given at least six (6) months prior to the end of the original term or additional term, as the case may be, which said party giving such notice desires to be the final term of this Agreement. At the end of the final term of this agreement, whether same be at the end of the original term or at the end of a renewal term, Owner shall, at its own expense disconnect, reconstruct, remove or modify such sewer mains and sewer main connections as City shall deem necessary to prohibit the flow of Owner's sewage into the sewer system of City and to assure the City's continued use of the perpetual easements and licenses granted to it in this Agreement.

## IX

The failure of either party to exercise its rights upon any default by the other shall not constitute a waiver of such rights as to any subsequent default.

## X

A listing of the Schedule of Exhibits hereto is as follows:

Exhibit "A": Final Plat of Lot 1, Echo Hills Replat 5  
Exhibit "B": Illustration of Sewer system of the Owner

## XI

If any provisions of this Agreement are held invalid or unconstitutional, such invalidity or unconstitutionality shall not affect other provisions of this Agreement which can be given effect without the invalid or unconstitutional provision and to this end, each paragraph, sentence and clause of this Agreement shall be deemed severable; provided, however, that, If in the sole opinion of City, the removal or inoperative effect of any such provision so declared invalid or unconstitutional shall materially affect City's rights hereunder, then City may terminate this Agreement, effective as of the date of City's written notice; whereupon the Owner shall:

- A. Pay to City all sums due under the terms of this Agreement to City at the time of termination, including all connection fees and sewer use fees accrued as of said date.
- B. At Owner's own expense, disconnect, reconstruct, remove or modify such sewer mains and sewer main connections, as City shall deem necessary to prohibit the flow of the Owner's sewage into the sewer system of the City.

## XII

Both parties acknowledge and agree that this written Agreement, including all exhibits hereto, constitutes the entire agreement of the parties and that there are no warranties, representations, terms or conditions other than those set forth herein.

## XII

The provisions of this Agreement shall be binding upon the parties hereto and their successors.

IN WITNESS WHEREOF, we, the parties hereto, by our respective duly authorized agents, hereto affix our signatures at La Vista, Nebraska, the day and year first above written.

ATTEST:

CITY OF LA VISTA, a municipal corporation  
in the State of Nebraska

CITY CLERK

BY: MAYOR

Echo Hills Apartments LLC

By:

Its: Owner

By: \_\_\_\_\_


STATE OF NEBRASKA )  
COUNTY OF \_\_\_\_\_ ) ss.  
                      )

On this \_\_\_\_\_ day of \_\_\_\_\_, 2022 before me, a  
Notary Public, duly commissioned and qualified in and for said County,  
appeared \_\_\_\_\_, of \_\_\_\_\_,  
personally known to me to be the \_\_\_\_\_ and the  
identical person whose name is affixed to the foregoing Subdivision Agreement, and  
acknowledged the execution therof to be his voluntary act and deed, and the voluntary act and  
deed of said Company.

WITNESS my hand and Notarial Seal the day and year last above written.

---

Notary Public



Job Number: 2142-102

thompson, dreessen & dorner, inc.  
10836 Old Mill Rd  
Omaha, NE 68154  
p.402.330.8860 www.td2co.com

Date: 03-25-22  
Drawn By: TDV  
Reviewed By: TDV  
Revision Date: ..

Echo Hills Replat 4 & 5, Lot 1

Exhibit B  
Sanitary Sewer System

# Exhibit J

## DRAFT

**POST CONSTRUCTION STORMWATER MANAGEMENT PLAN  
MAINTENANCE AGREEMENT  
LAV-20200408-5420-P**

**WHEREAS**, Echo Hills Apartments L.L.C., recognizes that storm water management facilities (hereinafter referred to as “the facility” or “facilities”) must be maintained for the development located at 7457 S 146<sup>th</sup> Street in the zoning jurisdiction of the City of La Vista, Sarpy County, Nebraska; and,

**WHEREAS**, Echo Hills Apartments L.L.C., is the owner of the property described on Exhibit “A” attached hereto (hereinafter referred to as “the Property Owner”), and,

**WHEREAS**, the City of La Vista (hereinafter referred to as “the City”) requires and the Property Owner, and its administrators, executors, successors, heirs, tenants or assigns, agree that the health, safety and welfare of the citizens of the City require that the facilities be constructed and maintained on the property, and,

**WHEREAS**, the Post Construction Stormwater Management Plan, (hereinafter referred to as “PCSMP”), shall be constructed and maintained by the Property Owner, its administrators, executors, successors, heirs, or assigns.

**NOW, THEREFORE**, in consideration of the foregoing premises, the covenants contained herein, and the following terms and conditions, the Property Owner agrees as follows:

1. The facility or facilities shall be constructed by the Property Owner in accordance with the PCSMP, which has been reviewed and accepted by the City of La Vista or its designee.
2. The Property Owner must develop and provide the “BMP Maintenance Requirements”, attached here to as Exhibit “B”, which have been reviewed and accepted by the City of La Vista or its designee. The BMP Maintenance Requirements shall describe the specific maintenance practices to be performed for the facilities and include a schedule for implementation of these practices. The BMP Maintenance Requirements shall indicate that the facility or facilities shall be inspected by a professional qualified in stormwater BMP function and maintenance at least annually to ensure that it is operating properly. A written record of inspection results and any maintenance work shall be maintained and available for review by the City. Records shall be maintained for a period of three years.
3. The Property Owner, its administrators, executors, successors, heirs, or assigns, shall construct and perpetually operate and maintain, at its sole expense, the facilities in strict

accordance with the attached BMP Maintenance Requirements accepted by the City of La Vista or its designee.

4. The Property Owner, its administrators, executors, successors, heirs, tenants or assigns hereby grants permission to the City, its authorized agents and employees, to enter upon the property and to inspect the facilities whenever the City deems necessary. The City shall provide the Owner copies of the inspection findings and a directive to commence with the repairs if necessary. The City will require the Property Owner to provide, within 7 calendar days from the date of City's written directive, a written response addressing what actions will be taken to correct any deficiencies and provide a schedule of repairs within a reasonable time frame. Whenever possible, the City shall provide notice prior to entry. The City shall indemnify and hold the Property Owner harmless from any damage by reason of the City's negligent or intentional acts during such entry upon the property.
5. The Property Owner its administrators, executors, successors, heirs, tenants or assigns, agrees that should it fail to correct any defects in the facility or facilities within reasonable time frame agreed to in the response by the Property Owner for corrective actions, or shall fail to maintain the structure in accordance with the attached BMP Maintenance Requirements and with the law and applicable executive regulation or, in the event of an emergency as determined by the City or its designee in its sole discretion, the City or its designee is authorized to enter the property to make all repairs, and to perform all maintenance, construction and reconstruction as the City or its designee deems necessary. Notwithstanding the foregoing, the City shall indemnify and hold the Property Owner harmless from any damage by reason of the City's negligent or intentional acts during such entry upon the property.
6. The City or its designee shall have the right to recover from the Property Owner any and all reasonable costs the City expends to maintain or repair the facility or facilities or to correct any operational deficiencies subject to the provisions of the immediately preceding sentence relating to negligence or intentional acts of the City. Failure to pay the City or its designee all of its expended costs, after forty-five days written notice, shall constitute a breach of the agreement. The City or its designee shall thereafter be entitled to bring an action against the Property Owner to pay, or foreclose upon the lien hereby authorized by this agreement against the property, or both. Interest, collection costs, and reasonable attorney fees shall be added to the recovery to the successful party.
7. The Property Owner shall not obligate the City to maintain or repair the facility or facilities, and the City shall not be liable to any person for the condition or operation of the facility or facilities.
8. The Property Owner, its administrators, executors, successors, heirs, or assigns, hereby indemnifies and holds harmless the City and its authorized agents and employees for any and all damages, accidents, casualties, occurrences or claims that may arise or be asserted against the City from the construction, presence, existence or maintenance of the facility or facilities by the Property Owner. In the event a claim is asserted against the City, its authorized agents or employees, the City shall promptly notify the Property Owner and the Property Owner shall defend at its own expense any suit based on such claim unless due solely to the negligence of the City in which event the City shall be required to defend any such suit at its own expense. Notwithstanding the foregoing, if any claims are made against both the City and the Property Owner, each will be required to defend any such suit or claim against it at its own expense. Each shall be responsible for payment of any recovery to the extent determined in such suit. If any judgment or claims against the City, its authorized agents or employees shall be allowed, the Property Owner shall pay for all costs and expenses in connection herewith except to the extent of the negligence or intentional act of the City.
9. The Property Owner shall not in any way diminish, limit, or restrict the right of the City to enforce any of its ordinances as authorized by law.
10. This Agreement shall be recorded with the Register of Deeds of Sarpy County, Nebraska and shall constitute a covenant running with the land and shall be binding on the Property

Owner, its administrators, executors, successors, heirs, or assigns, including any homeowners or business association and any other successors in interest.

IN WITNESS WHEREOF, Kevin James, of **Echo Hills Apartments L.L.C.** has executed this agreement this \_\_\_\_\_ day of \_\_\_\_\_, 2022.

**INDIVIDUAL, PARTNERSHIP and/or CORPORATION**

**Echo Hills Apartments L.L.C.**

Name of Individual, Partnership and/or Corporation

**Kevin James**

Name

Title

Signature

Name of Individual, Partnership and/or Corporation

Name

Title

Signature

**ACKNOWLEDGMENT**

State

County


On this \_\_\_\_\_ day of \_\_\_\_\_, 2022 before me, \_\_\_\_\_  
a Notary Public, in and for said County, personally came the above named: \_\_\_\_\_  
who is personally known to me to be the identical person whose name is affixed to the above  
instrument and acknowledged the instrument to be his, her (their) voluntary act and deed for the  
purpose therein stated.

WITNESS my hand and Notarial Seal the day and year last above written.

\_\_\_\_\_  
**Notary Public**

\_\_\_\_\_  
**Notary Seal**

## EXHIBIT 'A'



### PROJECT INFORMATION

Legal Description:

Lot 1, Echo Hills Replat 5, and Lot 1, Echo Hills Replat 4, a Subdivision in Sarpy County, Nebraska.

Property Address:

144<sup>th</sup> & Echo Hills Drive  
La Vista, NE 68138

Subdivision Name:

Echo Hills

Section:

NW 14-11-14

### APPLICANT INFORMATION

Business Name:

**Echo Hills Apartments L.L.C.**

Business Address:

129 N. 10<sup>th</sup> Street Unit 106  
Lincoln, NE 68508

Representatives Name:

Mr. Kevin James

Representative's Email:

kevinjames84@yahoo.com

Representative's Phone:

(402) 826-9393

### BMP INFORMATION

Name	Identifier	Latitude/Longitude	State Plane Coords.
EDDB-1	Extended Dry Detention Basin	N41.18383° W96.14074°	N 515616.654 E 2702000.591
DB-2	Detention Basin	N41.18553° W96.14038°	N 516197.778 E 2702098.210
DB-3	Detention Basin	N41.18530° W96.14017°	N 516171.592 E 2702193.118

**Exhibit "B"**

**BMP Maintenance Plan  
Echo Hills Apartments L.L.C.  
Lot 1, Echo Hills Replat 5  
Lot 1, Echo Hills Replat 4  
LAV-20200408-5420-P**

**Name & Location**

Project Name: Echo Hills  
Address: 144<sup>th</sup> & Echo Hills Drive  
PCWP Project Number: LAV 20200408-5420-GP1  
PCSMP Project Number: LAV 20200408-5420-P

**Site Data**

Total Site Area: 12.43 Acres  
Total Disturbed Area: 12.43 Acres  
Total Undisturbed Area: 0.00 Acres  
Impervious Area Before Construction: 0 %  
Impervious Area After Construction: 65 %

**Routine Maintenance and Tasks Schedule**

**Extended Dry Detention Basin and Detention Basin Maintenance Tasks and Schedules**

<b>Task</b>	<b>Schedule</b>
Remove debris and trash from basin and side slopes	Monthly
Outlet/inlet inspection and cleanout	Monthly
Bank mowing and inspection/stabilization of eroded areas	Monthly
Remove woody vegetation along embankment	Annually
Inspect for structural damage	Annually
Inspect, exercise all mechanical devices	Annually
Repair broken pipes	As needed
Replace filtration riprap that has been choked with sediment	As needed
Security	As needed